Concept: from the herringbone to the MindLine

The narrative runs "from the herringbone to the Knowing-Doing Line". In 1909 Zhan Tianyou crossed the Guangou ravines with one herringbone switchback; in 2026 the corridor crosses the watershed of the intelligent age with knowing and doing together — knowing first, because the humanities decide how far technology should go.

- **1909** — Self-reliant engineering
  A herringbone over the ravines ・ Bell Station to the southern gateway
- **Mid-20th c.** — Academic lineage
  Eight colleges and state institutes ・ Western Xueyuan Road segment
- **Late 20th c.** — Market innovation
  The spontaneous Electronics Street ・ West Meridian service wing
- **Today** — AI-Native
  Open source, compute, agents ・ Origin and Vanguard Stations
- **Next** — Unity of knowing and doing
  The MindLine ・ The whole belt as a network

Naming system

Layer	Name	Note
Parent brand	The MindLine	One identity and one narrative for the belt
Node layer	Vanguard / Origin / Bell (Mind Stations)	Continuing the memory of the railway station
Corridor layer	West Meridian / East Meridian	Service wing and scenario-enablement wing
Event layer	MindLine Summit	Parent brand for the annual flagship
Community layer	Loco Lab	The railway locomotive shed read as a model workshop
Digital assets	#MindLineBJ / the mindline family	One name online and on the ground

Loco Green #1E5945 · Mind Purple #7C4DFF · Compute Blue #5B8DEF · Warm Stone #F5F2EC · Ink #2B2B2B

Identity work here is directional only; no final trademark is delivered. The core figure abstracts the Qinglongqiao switchback: two rails form the character for "human", the first stroke reading as knowing and the second as doing, each leaning on the other so that together they stand as a person. The pair also reads as a circuit trace and a synapse, apex upward — a people-first ascending line. In motion the knowing rail and the doing rail can carry a data-flow animation with stations lighting up on ecosystem events; the minimal static form is simply the double-rail 人 symbol.

Stated limits

Stated limits: no unlicensed typeface, image, trademark or personal likeness is used; no existing corporate or park identity is copied; the cultural sign system and the parent identity stay in separate layers and are never mixed.

Fig. 1 Overall spatial structure: one spine, three stations, two wings



Overall spatial structure: one spine, three stations, two wings

The concept is one spine, three stations and two wings, stitching east to west and running through north to south. The spine is the linear green corridor of the Jing-Zhang Heritage Park, from Xizhimenwai Avenue in the south to the North Fifth Ring Road, with a recomputed walking and cycling spine of 9.60 kilometres — the shared physical carrier of the cultural, experience and innovation belts.

1141.28	43.61	369.29	9.60
Overall Design Area (hectares)	Coordinated Research Area (sq km)	Three Key Areas, total (ha)	Walking and cycling spine (km)
21.77	**3.55**	**12**	**3**
Green ratio (recomputed)	Public space share	AI scenario cards	AI pilgrimage landmarks

One spine — the MindLine corridor

The linear green corridor of the Heritage Park runs the full length and carries the cultural, experience and innovation belts together. It is also the body of the "computable park": rails, ballast and milestone markers retained, with an interactive AI installation band set between them.

Three stations — research, ecosystem, business

Vanguard in the north carries compute, foundation models and pilot production; Origin in the middle carries the open-source ecosystem, developers and a talent community; Bell in the south carries AI-Native business formats and international exchange — a walkable gradient of functions.

The three scope levels and three Key Areas shown are Provisional Boundaries, drawn as low-contrast dashed lines. Once official polygons are released, every geometry and metric must be recomputed.

Fig. 2 Land use structure and shares, recomputed in EPSG:4548



Land use structure and recalculation

The land use structure follows the existing fabric and is expressed as conceptual zoning in seven categories: the central MindLine corridor runs the full length as park green space, while the eastern and western bands carry research and education, commercial services, housing and community services according to the station segment. About 3.32 per cent is kept as reserved land against the uncertainty of AI-Native business formats. The union of all 50 land use cells equals the Overall Design Area, with no overlap between any two.

Land use category	Area (ha)	Share
Residential	343.24	30.07%
Green and open space	248.45	21.77%
Research and education	194.78	17.07%
Public administration and services	152.37	13.35%
Commercial services	147.56	12.93%
Reserved land	37.95	3.32%
Urban road land	16.94	1.48%

30% · 22% · 17% · 13% · 13%

The flywheel of the three positions

Centennial Jing-Zhang cultural belt

Narrative and place

Urban AI living experience belt

AI as perceptible everyday life

AI integrated innovation belt

Feedback turned into iteration

The three positions are not parallel slogans but a flywheel: the cultural belt supplies narrative and place, the experience belt turns AI into perceptible daily life, the innovation belt converts that feedback into technical iteration, and new technology feeds cultural expression in turn.

Fig. 3 Cluster fabric and landmark index of the three Key Areas



Detailed design of the three Key Areas

Each Key Area is developed in seven parts: position, spatial structure, building renewal, mobility, public space, AI scenarios and delivery risk. Because the three polygons are Provisional Boundaries, every conclusion below is directional and must be re-sited once official boundaries are released.

Vanguard Station

192.92 ha

Position

A garden-type full-stack innovation district. The Chinese name recalls the lineage running from Zhan Tianyou's self-built railway to today's full-stack autonomy.

Spatial structure

The corridor is the spine, with one cluster to each side: the western cluster holds full-stack research (ten conceptual footprints for research, laboratories and incubation); the eastern cluster holds compute and pilot production (ten footprints including a mobility hub, retail and talent apartments). A station plaza of about 5.01 hectares links the two.

Building renewal

New catalyst buildings and quality upgrading dominate; retention concentrates on railway memory objects beside the corridor. With no existing-building survey available, no demolition target is listed.

Mobility

Vehicles use an internal branch loop; walking and cycling rely entirely on the corridor spine and the cycle line. External links run through the rail connection segment pointing towards Shangdi and Qinghe.

Public space and landmark

The station plaza carries REN Gate; the green space carries the embodied-robotics public service testing ground, combined with a low-carbon setting for informal exchange.

Origin Station

104.32 ha

Position

A campus-adjacent open-source and talent community — the origin point for global developers, and the first segment in the phasing sequence.

Spatial structure

The western cluster is a developers' living cluster (six footprints mixing talent apartments, community services, incubation, education and retail); the eastern cluster is the open-source ecosystem cluster (six footprints for incubation, research, offices, laboratories and a mobility hub). The land use layer mixes research, education, housing and commerce in a campus-adjacent structure.

Building renewal

Organised as retain, renovate and build: campus and housing fabric retained, ground-floor frontages and boundary walls renovated, open-source release and talent-service catalysts newly built. The proportions await an existing-conditions survey.

Mobility

The core move is stitching campus, park and neighbourhood for pedestrians, carried by the internal branch loop together with the rail connection segment towards Wudaokou.

Public space and landmark

The station plaza of about 4.91 hectares carries Token Zero / Contributors' Walk; the Loco Lab developers' plaza is the community's everyday living room.

Bell Station

72.05 ha

Position

An urban district of AI-Native business formats and international exchange, named for the ancient bell of Dazhongsi.

Spatial structure

The western cluster is cultural (four footprints for culture, retail, mixed use and community services); the eastern cluster is AI-Native commerce (four footprints for mixed use, retail, offices and a mobility hub). The land use layer places cultural land next to commercial service land.

Building renewal

Quality upgrading dominates, focused on ground-floor uses and public frontages. Nothing is proposed inside heritage protection areas; all conceptual structures sit outside them, with the actual extent to be defined by the heritage authority.

Mobility

The core moves are station-city integration and four-quadrant pedestrian connection at the junction, carried by the rail connection segment towards Dazhongsi station and the internal branch loop. The form of the four-quadrant connection needs transport and municipal engineering study.

Public space and landmark

The station plaza of about 5.02 hectares carries The Resonance Bell; the market plaza carries AI-Native commercial activity.

The three polygons are Provisional Boundaries and every conclusion is directional: no parcel-level retain-renovate-demolish decision, no Floor Area Ratio or height figure, no engineering conclusion.

Fig. 4 Mobility, blue-green network and AI scenario nodes



Mobility, blue-green network and AI scenarios

The walking spine and the cycle line run in parallel for 9.60 kilometres each. The conceptual network holds 25 road centrelines totalling 53.84 kilometres, using only editable classes — secondary, branch, local access, pedestrian, cycleway, greenway and transit connection. No expressway or arterial is added.

— Stitching: eight east-west stitch nodes along the corridor as Conceptual Recommendations, one every 500 to 800 metres. Each is paired: a doing courtyard and a knowing courtyard. Crossing form needs transport and municipal study.

— Station-city integration: rail connection segments are proposed towards the Line 13 corridor of Dazhongsi, Zhichunlu and Wudaokou, with every segment kept inside the site.

Twelve scenario cards and three testing grounds

No.	Scenario card	Location	Privacy and Human Review boundary
SC-01	Heritage Park AI companion guide	Whole corridor SN-001	No facial recognition; voice processed locally and discarded
SC-02	Accessible AI wayfinding companion	Southern corridor SN-002	Location valid for this trip only; staff can take over at any time
SC-03	AI-Native market	Bell Station SN-003	Payment data never feeds cross-scenario profiling
SC-04	24-hour model study room and night school	Origin Station SN-004	Code and model weights belong to their contributors
SC-05	Urban multi-agent service portal	Origin Station SN-005	Human Review as backstop; full appeal route preserved
SC-06	AI health station	Dazhongsi community SN-006	Advice only, never diagnosis; anomalies escalate to staff
SC-07	Xiaoyue River smart waterfront	East Meridian SN-007	Environmental data fully open; no personal data collected
SC-08	Micro-circulation shuttle corridor	Mid-corridor SN-008	In-vehicle imagery for incident evidence only, limited retention
SC-09	Robot-friendly street	Vanguard Station SN-009	Robot identity and operator publicly displayed
SC-10	AI urban memory museum	Bell Station SN-010	Generated content labelled with historical sources
SC-11	Bilingual AI urban interface	Signage along the belt SN-011	No query history retained
SC-12	Energy-carbon dashboard	Vanguard Station SN-012	Aggregated to district level, never to the household

T1 Zhongzhiyuan embodied-robotics public service testing ground SN-013

A bookable test zone in the green space at Vanguard Station for guidance, cleaning, inspection and emergency assistance. Test windows and hoarding must be published, and the public may avoid the area.

T2 Autonomous micro-circulation shuttle test segment SN-014

A low-speed shuttle test segment in the middle of the corridor, physically separated from the walking spine. A safety operator is required and every takeover enters a public log.

T3 City-scale multi-agent collaborative governance sandbox SN-015

Built on synthetic data and a trusted data space, simulating multi-agent coordination for event safety, asset maintenance and service response. No real personal data is connected; outputs serve rehearsal only.

Four hard boundaries — spatial requirements, not only operating terms

1. Refusable: opt out at any time; a non-AI equivalent and a staffed counter remain.
2. Contestable: responsible party and complaint route displayed; AI content labelled.
3. Data minimisation: environmental data open, personal data not collected by default, sensors disclosed.
4. Accessibility parity: AI must not lower accessibility; every card passes review.

Fig. 5 Core metric recalculation and evidence dashboard



23 / 23
Mandatory requirements covered

5 / 5
Mandatory standards addressed

15 / 15
Design-depth items complete

37 / 37
Self-checks passed, no blocking failure

Scope	Official announcement	Recomputed, EPSG:4548	Deviation
Overall Design Area	about 11.4 sq km	1141.28 ha	+0.11%
Coordinated Research Area	about 43.6 sq km	43.61 sq km	+0.02%
Three Key Areas, total	about 368.4 ha	369.29 ha	+0.24%

Phasing 2026 - 2035

P1 2026 - 2028 — 502.87 ha ・ 44.1%

Origin demonstration segment

P2 2028 - 2032 — 225.92 ha ・ 19.8%

Three stations in concert

P3 2032 - 2035 — 412.49 ha ・ 36.1%

A complete network and regional integration

Source list — public materials or user-cleared materials only

1. Pre-qualification announcement (Haidian Branch, BMCPNR, 9 May 2026) 2. Agent open-call taskbook (user-cleared, 18 May 2026) 3. Urban Design Administrative Measures (MOHURD) 4. Regulatory Detailed Planning requirements (MOHURD) 5. Land and sea use classification guide (MNR, Nov 2023) 6. Provisional polygons for the scopes and Key Areas (5 June 2026) 7. Background: three-zone two-wing pattern; Haidian 1+X+1

Pending metrics and compliance limits

Five control metrics — Floor Area Ratio, total gross floor area, maximum building height, building density and the official green ratio target — are registered unknown and await official regulatory conditions. No estimated value is substituted.