


JING-ZHANG ONE MILLIMETER

Turn urban ambition into verifiable, maintainable and reversible action


Railway culture supplies calibration, Zhongguancun supplies experimentation, and AI must supply evidence and human accountability.

1 SPINE / 3 HUBS / 4 CONTINUITIES
one evidence spine · three differentiated hubs · four public continuities



One millimetre is a civic grammar, not a slogan of size

Calibration aligns language; interfaces protect rights; cycles build evidence; commitments assign responsibility



One Millimeter is first a common calibration. The Jing-Zhang Railway used shared gauge, mileage, and timetables to connect different places and professions as one system. The proposal borrows this engineering culture without turning railway imagery into decoration. Researchers, firms, operators, and the public use the same project ID, version record, spatial boundary, and evaluation language. When a result moves from laboratory to street, its method, limitations, maintenance cost, and failures move with it; a change of venue cannot erase the evidence trail.

It is also a public interface. Technology may improve efficiency, but it cannot cross the baseline of human rights and usable public space. Continuous accessibility, non-digital service, informed participation and withdrawal, final professional authority, heritage safety, and site restoration precede automation. AI equipment is therefore not the spatial protagonist. It is a switchable service layer attached to routes, waiting, learning, staffed service, and maintenance. The tighter the site, the stronger the priority given to public passage and human support.

Separate fact, correction, inference and unknown before claiming design depth

Every analytical drawing states its source, valid scope and the data still required

The proposal distinguishes citable facts, a user-corrected site condition, provisional inputs used for exploration, and professional data that must still be obtained. Citable facts include the public announcement, Agent Taskbook, announced areas, and names of the three key areas. The corrected condition is that the key parcels have no existing surface-water system. Provisional inputs include rough repository boundaries and concept layers used only to test spatial relationships. Missing professional inputs include official boundaries, 1:500 or 1:2000 survey, ownership, building audit, heritage controls, roads and transit exits, underground utilities, tree survey, thermal environment, lighting, and an operating budget.

This distinction controls the level of claim. The plan may recommend a continuous accessible spine, three reversible test courtyards, and open ground-floor interfaces. It cannot infer demolition, floor-area ratio, or quantities. Earlier water imagery is withdrawn. Ordinary rainfall is handled by existing municipal drainage, tree pits, and paving construction, but the proposal does not rebrand drainage infrastructure as a site water system or claim storage performance. Renderings communicate future spatial intention; they do not document existing conditions or imply government approval.

The narrative explains judgments and strategies. Drawings explain spatial organisation. GeoJSON stores recomputable concept geometry. Metrics, assumptions, standards, and compliance matrices define the evidence boundary. A number without a traceable source or formula does not enter the conclusion. A spatial move without an owner and stop condition does not enter the near-term implementation package.

JUDGEMENT

Every analytical drawing states its source, valid scope and the

SPATIAL MOVE

Start with the smallest reversible move; expand only


PASS CONDITION

Ordinary space remains usable, ownership is named,

ANALYSIS 02

Separate fact, correction, test and unknown

Evidence strength—not graphic completeness—determines design depth



The closera decision is to construction, the stronger its evidence must be; renderings never fill unknowns.

Source: public call brief, agent taskbook and proposal working data; design-analysis basis only

JING-ZHANG ONE MILLIMETER

No existing surface-water system: withdraw the false narrative and refocus the design

Replace invented water with access continuity, railway heritage, shade and public ground floors

The key parcels have no existing surface-water system. The design can no longer use riverbanks, wetlands, waterfront access, or a “blue-green corridor” as a shortcut. The actual tasks are more urban and more demanding: the railway heritage space is broken by roads, walls, and management boundaries; accessible movement lacks continuity; ground floors offer few places to wait or obtain public service; research results lack settings for real use; and event activity lacks a long-term maintenance system. Resources are therefore concentrated on six verifiable jobs: repair continuous movement, retain railway fabric, add shade and seating, create dry material and facility test settings, open staffed public ground floors, and organise year-round operation.

The correction also changes the rules for renderings. No image may show a river, lake, canal, wetland, or landscape pool that is absent from the site. Green space is made from existing-tree protection, additional canopy, drought-tolerant groundcover, breathable paving, and removable seating. Drainage grates, inlets, and tree pits appear only as ordinary construction, not as a cultural theme. Every image must show where people enter, how they move and wait, who works there, how equipment is maintained, and whether the place still functions after an event ends.


A dry site still faces Beijing summer heat, short rain events, winter wind, and daily dust. Those issues are evaluated separately through shade continuity, surface temperature, drainage clearance, durable paving, winter accessibility, and maintenance hours. The design object shifts from an abstract ecological waterscape to measurable public-space performance, which is both more truthful and more implementable.

JUDGEMENT	SPATIAL MOVE	PASS CONDITION
Replace invented water with access continuity, railway	Start with the smallest reversible move; expand only	Ordinary space remains usable, ownership is named,

ANALYSIS 03

Correctinga dry site

Withdraw the water narrative and refocus on access, shade, service and upkeep




Source: public call brief, agent taskbook and proposal working data; design-analysis basis only

JING-ZHANG ONE MILLIMETER

Three scales form one responsibility chain

43.6 km² sets the mechanism, 11.4 km² the structure, and three key areas the near-term demonstrators



The three scopes are not the same drawing at three scales. They answer why an innovation belt is needed, how it is organised, and where the first projects can operate.

One project ID connects the three scales. A public problem is raised in the district; a research team establishes a method; a technology is tested in a bounded site; an operator records results; incubation and professional services organise the next step; public use and an annual audit decide whether to continue, revise, or stop. Strategy becomes operational and each hub avoids becoming an isolated showcase.

The three scales share one problem ledger. The regional scale records research infrastructure, industry services and finance interfaces; the corridor scale converts those resources into relationships among stations, neighbourhoods and the railway park; the key-area scale turns those relationships into near-term packages that can be procured and accepted. Each upper scale supplies resources, rules and review conditions rather than simply drawing a larger boundary.

Every node must therefore answer two questions: which break in the regional innovation chain does it repair, and which precise public interface does it improve? A local image-making exercise that cannot update the shared ledger does not proceed.

Six tasks must form one causal loop

Concept, ecosystem, scenario, space, culture and operations move one project from problem to evidence

The concept supplies a shared language. The innovation ecosystem defines how projects mature. AI-enabled scenarios place technology in real life. Public space makes testing accessible. The cultural narrative explains why it belongs to Jing-Zhang. Long-term operations keep space, content, and funding current. Together, the six tasks explain where a project begins, where it is tested, who is accountable, and what evidence remains.

The sequence makes the six tasks operational. The concept defines a shared test; the ecosystem identifies where projects originate; AI scenarios translate technical limits into real tasks; public space creates observable test interfaces; culture makes evidence legible; annual operations feed results back into the next project-selection cycle.


Each link hands a defined record to the next: a problem statement and owner, a service journey and risk boundary, a location and section, then upkeep orders and evaluation notes. If one record is missing, the chain pauses instead of hiding the gap with an event or publicity.

JUDGEMENT	SPATIAL MOVE	PASS CONDITION
Concept, ecosystem, scenario, space, culture and operations	Start with the smallest reversible move; expand only	Ordinary space remains usable, ownership is named,

ANALYSIS 05

Six tasks are not six separate lists

Concept, ecosystem, scenes, space, culture and operations form one causal loop



Each task enables the next; operating evidence returns to revise the concept and scenarios.

Source: public call brief, agent taskbook and proposal working data; design-analysis basis only

From clustering companies to clustering evidence

The scarce resource is not office area, but urban interfaces where research meets real problems



The scarce resource is not office floor area. It is an urban interface where basic research meets real problems, firms gain access to compliant test settings, and the public can understand technological consequences. The proposal defines a seven-gate chain: G0 public problem, G1 basic research, G2 shared technology, G3 scenario validation, G4 incubation and first user, G5 capital-readiness services, and G6 scaling and international collaboration. A project may advance, return, or stop. Passing a gate must add reviewable evidence, not promotional language.

Six global cases support mechanism choices rather than local numerical targets. Punggol Digital District shows how campuses, firms, and district operations can share a collaborative environment. Kalasatama demonstrates low-barrier, short-cycle district experiments. MIT Senseable City Lab connects research with governments and communities. Paris-Saclay integrates research, industry, mobility, and quality of life. Barcelona 22@ warns against reducing an innovation district to offices. Waterfront Toronto demonstrates independent digital review and public accountability. Jing-Zhang transfers openness, mixed use, review, and iteration; it does not copy foreign scale or import waterfront precedents into a dry site.

SEVEN GATES: REDUCE RISK BEFORE ENTERING THE

Every gate permits continuation, return, or stop



EVIDENCE	HUMAN DECISION	SPATIAL INTERFACE	EXIT + RESTORE
Problem card, model card, 30/90-day record, first-user acceptance, reuse pack	Professionals and site owners retain final judgment and stop authority	Qinghe validates, AI Origin translates, Dazhongsi reviews	Publish failure; remove equipment in one shift; preserve basic service

Seven gates connect research, incubation and capital services

Each gate adds reviewable evidence rather than another promotional claim

G5 does not promise investment. It makes a project legible to due diligence by organising ownership, compliance, user value, cost, risk, and maintenance in one data room. Capital follows real-world evidence instead of substituting funding excitement for public value.

Zhongzhiyuan leads research and safety validation. Beijing AI Origin Community translates results, hosts open-source maintenance, and supports talent. Dazhongsi hosts product experience, business exchange, and international presentation. Zhongguancun Technology Services Wing supplies intellectual-property, compliance, and capital-readiness services. The Agent Taskbook's Xiaoyue River Scenario Enablement Wing supplies public problems and community review; the name is treated as a district label and does not establish a surface-water condition in the key parcels. One project ID, Open Test Passport, and evidence repository preserve accountability across the five roles.

The gates are evidence thresholds that progressively reduce uncertainty, not a linear approval queue. They confirm a public problem, justify the method, prove a basic prototype, supervise first use, secure professional and public review, account for long-term upkeep, and only then permit capital to amplify a maintainable project.


A project may exit at any gate. Exit keeps an unsuitable technology at a safer experimental level; it is not treated as failure. Access to space, capital and public visibility follows evidence maturity so fundraising capacity never substitutes for public-value judgement.

JUDGEMENT	SPATIAL MOVE	PASS CONDITION
Each gate adds reviewable evidence rather than another	Start with the smallest reversible move; expand only	Ordinary space remains usable, ownership is named,

ANALYSIS 06

Seven gates from research to capital services


A project advances only with evidence, an accountable owner and an exit rule



Source: public call brief, agent taskbook and proposal working data; design-analysis basis only

The nine-kilometre evidence spine: validate north, translate centre, amplify south

One corridor diagram assigns duties to each segment instead of colouring five isolated parks



The nine-kilometre spine is not a uniformly paved landscape. It is a continuous public evidence system. The northern section from Qinghe to Zhongzhiyuan focuses on research validation in quieter, controllable material and safety-testing spaces. The central section from AI Origin to Sitaokou translates prototypes into neighbourhood services and shares ground floors between open-source work, railway memory, and everyday life. The southern section from Dazhongsì toward Xizhimen gives mature projects high-access settings for public experience, business exchange, and international communication.

Four systems run through all three sections: a continuous accessible walking line protected from exhibits; a commuter cycling line that slows at conflict points; a heritage narrative line organised by retained tracks, sleepers, distance marks, and industrial components; and a shade-and-dry-ecology line made of retained trees, additional canopy, drought-tolerant planting, breathable paving, and repairable seating. The systems run side by side where space allows and overlap in narrow sections. AI equipment never interrupts basic movement.

Move beyond the park: cross-neighbourhood interfaces are the key


Stations, crossings, public ground floors and the heritage spine must form a walkable chain



The proposal is not confined to the heritage park. The spine is the address and evidence line; the actual innovation ecosystem occupies a sequence of cross-links, public ground floors, courtyards, service counters, and test rooms on both sides. Each hub therefore combines three layers: an uninterrupted public route on the railway edge, a staffed interface in the first row of buildings, and a deeper professional or industrial support space. A visitor can move from seeing a problem to finding the responsible team without crossing an invisible institutional boundary.


Cross-links are chosen by everyday demand, not by equal spacing. A link is justified when it connects a station exit, school, community, research campus, enterprise-service facility, or existing commercial street to the spine. Its minimum package is modest: a legible crossing, continuous accessible surface, shade or weather protection, night lighting, a non-digital direction sign, and a named maintainer. Only after these basics work may sensors, displays, or event equipment be added.

This structure also controls development pressure. The park remains a civic commons rather than a frontage for continuous commercialisation. Revenue-generating uses concentrate inside existing or legally adaptable buildings, while the railway edge carries passage, heritage interpretation, public review, and reversible prototypes. The distinction lets the plan support entrepreneurship without turning every metre of public space into an exhibition booth.



The 38-metre section is a compatibility test, not a uniform boundary

When space narrows, protect access, heritage, cycling and shade before events or equipment



The section places a 6 m public ground-floor edge, 4 m walk, 3.5 m cycle lane, 5 m dry shade-and-rest band, 9 m heritage-track or flexible field, a second 4 m walk, and a 3.5 m planted edge on one drawing. It tests whether seven demands can coexist. In narrow areas, the priority is continuous accessibility and heritage safety, followed by cycling, tree protection, and shaded waiting, with events and digital installations last. The five-metre band is not a water feature: it accommodates existing trees, new canopy where underground conditions allow, benches with companion wheelchair spaces, and removable material samples. Official road boundaries, viaduct clearance, fire access, and utilities require specialist review.

Step one repairs crossings, ramps, shade, night lighting, and non-digital wayfinding. Step two opens ground-floor interfaces as reservable workshops, service desks, and neighbourhood rooms. Step three inserts reversible prototypes such as material bays, shade seats, open-source galleries, and small stages. Step four determines retain, renovate, infill, or demolition only after a building audit. Public value appears early, while later capital works remain responsive to evidence. Each step has its own acceptance test, so a useful crossing or service counter does not have to wait for a landmark building.

JUDGEMENT	SPATIAL MOVE	PASS CONDITION
When space narrows, protect access, heritage, cycling and	Start with the smallest reversible move; expand only	Ordinary space remains usable, ownership is named,


Qinghe Materials Validation Court: make urban materials produce reproducible evidence

Three replaceable bays, one public observation route and a test boundary that can shut down



QINGHE MATERIALS COURT: THREE COMPARABLE TEST BAYS

Retain the rail and accessible route; separate equipment, observation, maintenance and removal paths



SPATIAL ACCEPTANCE CARD

01 COMPARABLE

Three materials share footfall, weather and recording rules

02 SEPARATE

Public observation never mixes with equipment servicing

03 DAY-90 PASS

Safety, comfort, access and labour are signed together


04 STOP

Remove on looseness, overheating, confusion or blocked passage

CONCEPT ONLY

JING-ZHANG ONE MILLIMETER

Concept spatial organisation based on provisional geometry; verify survey, tenure, heritage, trees and utilities before delivery.




Qinghe sits where industrial research, existing communities, and the heritage spine meet, making it suitable for G1 to G3. An approximately 180 m dry controlled test strip combines three replaceable material bays, an observation walk, a human-review desk, retained trees, and shaded waiting. It does not imitate a river edge. Sensors do not automatically produce a conclusion. Climate, surface temperature, wear, slip resistance, installation labour, and maintenance conditions are registered first; sensing and manual observation are compared; inputs, failed samples, and the continue-or-stop decision are then published. Researchers gain a real setting, visitors see how conclusions are made, and park operators receive maintainable work orders rather than a black-box dashboard.

The first package tests only non-personal-data applications such as paving durability, summer surface temperature, shade performance, tree-pit maintenance, seating repair, and facility condition. The three bays use the same base and exposure period so that materials can be compared fairly. A sample is retained only when it meets public-safety thresholds, its labour and replacement cost are disclosed, and the site team accepts a 90-day maintenance duty. Ordinary drainage remains conventional municipal engineering and is not presented as a design attraction.

During a normal weekday, one bay may be under controlled wear testing, one open for supervised public observation, and one closed for replacement. Visitors never walk through the test itself: a parallel accessible route and low evidence rail show the question, method, current status, and accountable person. This makes failure visible without converting the place into an unsafe laboratory.

AI Origin Shared Courtyard: turn prototypes into maintained public products

Open-source work, maintainers, first users and staffed service share one public interface





AI Origin serves G3 to G5 and translates research into neighbourhood and incubation services. Its core is an approximately 120 m railway heritage interface. A continuous 4.5 m accessible route connects the open-source gallery, maintainer table, talent-service desk, and dry shared courtyard with trees and removable shade. A project receives exhibition space only after stating the problem, data, maintainer, failure mode, and equivalent human service. The courtyard is therefore not a technology showroom; it is the point where a prototype obtains a real user, an operating commitment, and a public record.

By day, the courtyard is a talent and company-service entrance. In the evening, it hosts community classes and maintainer clinics. Release events use reversible trackside frames without closing the basic route. Value is measured by prototypes accepted by first users, maintained for 90 days, and documented clearly, not by the number of displays.

Four visible roles prevent responsibility from dissolving. The problem owner explains why the task matters; the maintainer controls the version and defect list; the first user confirms whether the service fits real work; and an independent reviewer can pause the trial. Their names, contact routes, and decision dates appear together on the same evidence card. If any role is vacant, the project may be discussed indoors but cannot occupy public space.

Dazhongshi One-Millimetre Stage: expose mature services to public and market review

The same task offers an ordinary staffed route and an optional AI-assisted route



Dazhongsi's transit access, commerce, and dense daily life suit G4 to G6. An approximately 90 m flexible event edge, a 6 m open ground-floor zone, and retained tracks support four states. Weekdays host staffed healthcare-navigation, education, and commercial service trials. Evenings use low-glare lighting and small discussion tables without disturbing the through route. Weekends support an open-source market maintained by developers and neighbours. The annual Open Week becomes a bilingual release and cross-city collaboration setting. None of these states depends on a water feature or a permanent spectacle.

The “stage” is not a giant screen. Its essential elements are removable canopies, low information bands, staffed service desks, accessible waiting areas, and switchable temporary power. Events preserve daily movement and define capacity, noise, fire safety, photography, and data permissions. Sponsors do not replace professional reviewers.

The spatial test is whether the place remains useful after the event. Can a resident still cross it directly? Can a wheelchair user wait beside a companion? Can equipment be removed within one shift? Can nearby shops continue operating, and can a complaint reach a named duty manager? These questions turn the southern gateway from an image-making stage into a reliable civic interface.

Developer Walk: place versions, failures and upkeep in the night-time public realm

Every display traces the problem, method, failure, human review and named maintainer




The Developer Walk is a physical interface for understanding project lifecycles, not a QR-code trail. Four station types sit beside retained rails. Problem signs explain a public need; method signs state model and data limits; test signs identify the current version and accountable person; review signs record a decision to continue, revise, or stop. Paper, tactile, or staffed alternatives convey all essential information without requiring an app.

The Evidence Gallery displays only reusable work, including licence, operating conditions, maintainer, known defects, and reuse history. The Contribution Wall avoids popularity rankings. It recognises four forms of work: clarifying a real problem, merging a reusable version, completing independent validation, and maintaining or responsibly stopping a project. Entries can be appealed, corrected, and withdrawn, turning recognition into responsibility.

Low-glare lighting and recessed display units protect the clear walking width and the railway fabric. Each unit answers one question: what problem is addressed, which version is shown, where it failed, who reviewed it and who maintains it. A QR code is supplementary; the essential evidence remains readable without a phone.

Displays earn renewal rather than permanent occupation. At the end of a term, the maintainer submits evidence for retention, relocation or removal. An offline unit becomes a static panel rather than a black screen, bright nuisance or obstacle; bookings and sound limits protect ordinary evening life.


DEVELOPER WALK EVIDENCE CHAIN



A display is complete only when problem, version, failure, human review and maintainer are visible together.

Six user groups are simultaneous design constraints, not market segments

Researchers need reproducibility, residents need ordinary life, maintainers need shutdown control, and non-digital users need the same service




Residents need daily services that do not exclude non-digital users. Researchers need reproducible tests that can fail. Start-ups need a first user and a compliance path. District and park operators need maintainable facilities that can be shut down. Healthcare, education, legal, and accounting professionals retain final authority. International developers need bilingual documentation, clear licences, and tasks that support remote contribution. Every scenario states who benefits, who may be harmed, and who performs human takeover.


AI + healthcare: start with optional service navigation, not autonomous diagnosis

Space provides staffed help, quiet waiting, paper routes and clear referral before AI reduces information friction

HEALTH SERVICE JOURNEY: AI STOPS BEFORE CLINICAL DECISION



Red line: no diagnosis and no medical-record access; staffed service remains visible and users can exit.



The strength of a scenario does not come from its “AI content.” It comes from improving both service and space. AI healthcare places an accessible route, quiet waiting, privacy notice, staffed advice, and handover record in one journey. AI education turns railway engineering, material ageing, shade, accessibility, and maintenance into observable curricula rather than automating teaching. AI commerce makes firms, professional services, and first users share an accountable validation relationship instead of installing a large shopping screen.

Each scenario is written as an operating card with nine fields: the real problem, principal user, exact spatial interface, minimum physical service, data boundary, human decision-maker, failure mode, measurement method, and withdrawal condition. This prevents a generic chatbot from being counted as urban design. If the spatial interface, duty roster, or exit route is missing, the scenario remains a workshop topic and does not enter the public realm.

The three AI+ families use different thresholds. Healthcare prioritises privacy, accessibility, referral accuracy, and professional handover; it never diagnoses. Education prioritises teacher control, age-appropriate interpretation, and correction of public content; it never replaces teaching. Commerce prioritises voluntary trials, truthful performance statements, confidentiality, and a route to legal, intellectual-property, accounting, or capital specialists; it never gives an automated approval or investment conclusion.


The first sites are public-service foyers at community clinics, campus health stations or hospital approaches, never the consulting room. A staffed desk, quiet waiting zone, paper route, optional AI guide and visible referral exit form one continuous interface so older people, carers and non-digital users can complete the same task without a phone.

AI is limited to wayfinding, document guidance, queue explanation and language support. It does not diagnose, read unauthorised records or replace a clinical decision. Advice shows its source and update time; users can return to staff at any step, and disputed answers enter human review instead of another automated response.

AI + education: make the city an observable and reviewable classroom

Students observe real materials and shade; teachers review the task; AI only supports recording and comparison

CITY CLASSROOM: FROM OBSERVATION TO TEACHER REVIEW



AI only supports recording and comparison; teachers retain task definition, review and conclusion.



The strength of a scenario does not come from its “AI content.” It comes from improving both service and space. AI healthcare places an accessible route, quiet waiting, privacy notice, staffed advice, and handover record in one journey. AI education turns railway engineering, material ageing, shade, accessibility, and maintenance into observable curricula rather than automating teaching. AI commerce makes firms, professional services, and first users share an accountable validation relationship instead of installing a large shopping screen.

Each scenario is written as an operating card with nine fields: the real problem, principal user, exact spatial interface, minimum physical service, data boundary, human decision-maker, failure mode, measurement method, and withdrawal condition. This prevents a generic chatbot from being counted as urban design. If the spatial interface, duty roster, or exit route is missing, the scenario remains a workshop topic and does not enter the public realm.

The three AI+ families use different thresholds. Healthcare prioritises privacy, accessibility, referral accuracy, and professional handover; it never diagnoses. Education prioritises teacher control, age-appropriate interpretation, and correction of public content; it never replaces teaching. Commerce prioritises voluntary trials, truthful performance statements, confidentiality, and a route to legal, intellectual-property, accounting, or capital specialists; it never gives an automated approval or investment conclusion.


The classroom links the materials court, shade observation points and railway heritage nodes. Students use a common field sheet to record temperature, shade, wear, texture and use conflicts; AI can organise time series and comparisons, while teachers and specialists retain question setting, content review and conclusions.

A briefing zone, observation route, group review tables and public results board form the spatial sequence. The route remains outside test exclusion areas, and the board shows raw records, method and uncertainty so a polished model answer is never mistaken for fact. Data from minors is excluded from public display.

AI + commerce: trusted trials use the same task, queue and staffed fallback

Ordinary and AI-assisted service face the same task; users may opt out; firms disclose cost and upkeep

TRUSTED TRIAL: SAME TASK, SAME QUEUE, STAFF FALLBACK



Trials compare with ordinary service; opt-out, appeal, cost and upkeep are disclosed.



The strength of a scenario does not come from its “AI content.” It comes from improving both service and space. AI healthcare places an accessible route, quiet waiting, privacy notice, staffed advice, and handover record in one journey. AI education turns railway engineering, material ageing, shade, accessibility, and maintenance into observable curricula rather than automating teaching. AI commerce makes firms, professional services, and first users share an accountable validation relationship instead of installing a large shopping screen.

Each scenario is written as an operating card with nine fields: the real problem, principal user, exact spatial interface, minimum physical service, data boundary, human decision-maker, failure mode, measurement method, and withdrawal condition. This prevents a generic chatbot from being counted as urban design. If the spatial interface, duty roster, or exit route is missing, the scenario remains a workshop topic and does not enter the public realm.

The three AI+ families use different thresholds. Healthcare prioritises privacy, accessibility, referral accuracy, and professional handover; it never diagnoses. Education prioritises teacher control, age-appropriate interpretation, and correction of public content; it never replaces teaching. Commerce prioritises voluntary trials, truthful performance statements, confidentiality, and a route to legal, intellectual-property, accounting, or capital specialists; it never gives an automated approval or investment conclusion.

Trials occupy supervised public ground floors, event foyers and temporary bays in Dazhongsi, using comparable tasks such as ticketing, information, selection or after-sales help. Ordinary and AI-assisted services share the same task, queue and evaluation criteria; participants are informed before entry and may return to staff at any step.

The operator discloses price, data scope, accountable staff, upkeep cost and exit route. Colour and signage distinguish a trial from ordinary service; default consent and forced participation are prohibited. A failed device folds away or leaves the main route so everyday commerce continues.

Fifteen scenarios are risk-differentiated spatial interfaces, not a wish list

Materials and robotics validate in Qinghe, public services begin at Origin, and mature projects face public review at Dazhongsi

ANALYSIS 17

AI+ PLACEMENT: THREE SERVICES, THREE ACCOUNTABILITY PROTOCOLS

Healthcare, education and commerce answer spatial interface, human handover, data boundary and day-90 acceptance differently

AI + HEALTHCARE

SPACE

Staffed navigation desk + private handover room

HUMAN

Clinical decisions remain with registered professionals

DATA

No retention by default; minimum fields and timed consent

DAY 90

Handover time, misdirection and complaints; stop on any serious event

A HUMAN EXIT PATH IS MANDATORY

AI + EDUCATION

SPACE

Bookable class + teacher observation + opt-out seats

HUMAN

Teachers review content and decide classroom use

DATA

No default profiling of minors; work can be withdrawn

DAY 90

Comprehension, teacher labour and equity; stop if unexplainable

A HUMAN EXIT PATH IS MANDATORY

AI + COMMERCE

SPACE

Voluntary trial + visible price + staffed refund point

HUMAN

Merchant owns transaction, aftercare and disputes

DATA

Trial is separate from payment; no profile-based price discrimination

DAY 90

Conversion, refunds and misleading claims; stop on coercion

A HUMAN EXIT PATH IS MANDATORY

Concept spatial organisation based on provisional geometry; verify survey, tenure, heritage, trees and utilities before delivery.

JING-ZHANG ONE MILLIMETER

The strength of a scenario does not come from its “AI content.” It comes from improving both service and space. AI healthcare places an accessible route, quiet waiting, privacy notice, staffed advice, and handover record in one journey. AI education turns railway engineering, material ageing, shade, accessibility, and maintenance into observable curricula rather than automating teaching. AI commerce makes firms, professional services, and first users share an accountable validation relationship instead of installing a large shopping screen.


Each scenario is written as an operating card with nine fields: the real problem, principal user, exact spatial interface, minimum physical service, data boundary, human decision-maker, failure mode, measurement method, and withdrawal condition. This prevents a generic chatbot from being counted as urban design. If the spatial interface, duty roster, or exit route is missing, the scenario remains a workshop topic and does not enter the public realm.

The three AI+ families use different thresholds. Healthcare prioritises privacy, accessibility, referral accuracy, and professional handover; it never diagnoses. Education prioritises teacher control, age-appropriate interpretation, and correction of public content; it never replaces teaching. Commerce prioritises voluntary trials, truthful performance statements, confidentiality, and a route to legal, intellectual-property, accounting, or capital specialists; it never gives an automated approval or investment conclusion.

Mobility and new infrastructure: equipment yields to continuous public access

Walking, accessibility, cycling and rail transfer come first; equipment failure may never occupy the main route

MOVEMENT PRIORITY: EQUIPMENT ENTERS LAST



Later systems always yield; failed equipment may never occupy the first four movement levels.



The mobility order is walking and accessibility, cycling, transit connection, public transport, service and emergency vehicles, then general cars. The spine provides north-south continuity; cross-links at the three hubs repair barriers created by roads, viaducts, and closed edges. No event or trial occupies the accessible clear path. Cycling remains continuous in commuting sections and slows through surface, geometry, and sightlines where exhibits and crowds occur. Around stations, priority goes to the last 500 m of direction finding, sheltered waiting, shared-cycle order, and night safety. Exact alignments require exit, road-boundary, and transport assessment data.

Municipal and new infrastructure follow the rule that sensing is not control. Twelve environmental observation points are proposed in phases to collect only the minimum information needed for public-space operation, such as air and surface temperature, humidity, shade condition, equipment status, and manual inspection records. They do not measure an invented water body. Processing is local where possible and public output is aggregated. Stations may request inspection but cannot control drainage, transport, or public-safety systems. Lighting, temporary power, networking, and equipment cabinets use replaceable modules. Basic passage and human service survive power or network failure.

Public service is not a back-office room. Problem clinics, test registration, compliance advice, talent service, community deliberation, maintenance response, and non-digital assistance occupy visible, accessible ground-floor locations. Every digital interface has a phone, paper, or staffed alternative.

Public ecology without surface water: trees, root zones, shade and upkeep form the comfort network

Do not invent rivers or wetlands; improve performance through inspectable shade, breathable roots and maintenance orders



The green strategy starts from the corrected fact that the key parcels have no existing surface-water system. It therefore forms a dry network from retained trees, additional canopy where root and utility conditions permit, drought-tolerant groundcover, permeable but structurally verified paving, small planted pockets, and shaded resting points. Ordinary inlets, kerbs, and maintenance access remain visible and serviceable, but no river, wetland, canal, pond, or water court is invented as a spatial organiser.


Public space is organised in four layers. The first is the continuous everyday route that remains open during trials and events. The second is a sequence of six cultural stops that translates railway measurement, Zhongguancun experimentation, and accountable AI into physical actions. The third consists of three staffed hubs for testing, service, and public review. The fourth is a network of smaller cross-links and ground-floor rooms that carries benefits into surrounding neighbourhoods. Every layer has a basic non-digital function before any screen or sensor is added.

Urban character comes from construction logic rather than futuristic decoration. Retained rail, steel frames, dark mineral paving, bolted joints, repair marks, canopy shadows, and low evidence rails form a calm industrial base. Cyan identifies open interfaces, amber identifies pending human review, civic green identifies maintained public access, and magenta identifies provisional information. New work is dated and reversible so that it can be distinguished from heritage fabric. At night, light is concentrated on walking surfaces, entrances, and staffed interfaces; screens do not dominate the skyline.

ANALYSIS 10

A dry site can still deliver high-quality public ecology

Trees, root zones, shade, paving, drought planting and upkeep forma dry comfort network



Source: public call brief, agent taskbook and proposal working data; design-analysis basis only

JING-ZHANG ONE MILLIMETER

Eight reversible components share maintenance logic, not one repeated form

Each component can be installed, isolated, replaced and removed independently, with a named maintainer and failure state

ANALYSIS 18

ONE-MILLIMETRE KIT: EIGHT MAINTAINABLE PARTS

Share connection, service, shutdown and removal logic—not one repeated form

01

SHADE FRAME

02

SEAT + COMPANION BAY

03

EVIDENCE FRAME

04

STAFFED COUNTER

05

ROOT PROTECTION

06

MATERIAL TEST BAY

07


EQUIPMENT CABINET

08

STOP / EXIT FACE

Concept spatial organisation using provisional geometry; redraw from formal survey, tenure, heritage and utility data before implementation.

JING-ZHANG ONE MILLIMETER




The kit includes the One-Millimetre Gate, physical problem sign, material bay, removable shade seat, maintainer table, open-source display frame, human-review desk, and switchable power cabinet. Each identifies installation prerequisites, routine maintainer, failure state, and removal method. Rail steel, dark structures, and bolted joints recall railway engineering. Open cyan identifies shared data and interfaces; review amber marks pending human decisions; civic green marks maintained public access; provisional magenta marks uncertain boundaries and data. Words and symbols accompany colour for accessibility. The parts share fixings and dimensions so that a failed element can be replaced without rebuilding an entire place.

The kit is organised by interface standards rather than a uniform appearance. Footings, power, data, shade, drainage and access panels use legible connection rules so parts can be removed without damaging railway fabric or primary paving. Materials and scale may vary, but responsibility plates, failure states and replacement procedures do not.

Procurement records installation time, staffing needs, spare-part source, safe power-off state and end-of-life route. Pilot operation records real use and repair frequency; high-upkeep, low-use or obstructive parts are reduced or removed instead of becoming permanent because money has already been spent.

Six-stop cultural route: turn railway, Zhongguancun and AI culture into six actions

Culture is not decoration, but an action chain from measure and connect to test, open, review and return to life




Railway culture supplies measurement, connection, and maintenance. Zhongguancun culture supplies experimentation, translation, and entrepreneurial collaboration. AI culture requires openness, explanation, and human responsibility. The route is not a historical theme park. It moves visitors through measuring, connecting, testing, opening, reviewing, and returning technology to everyday life.

The international line is “Measure small. Learn in public. Improve with people.”

The stops follow actions, not a chronology: measure materials and climate at Qinghe; connect neighbourhoods at station interfaces; test public services at AI Origin; open versions and failures on Developer Walk; review mature projects at Dazhongsi; and return to ordinary community life. Each stop combines a heritage trace, a present task and evidence visitors can retain.


Ground calibration marks, low plaques, a paper foldout and optional digital media run in parallel. Screens never cover railway fabric, and a failed QR code does not prevent basic understanding. Group visits avoid commuting peaks; capacity and sound are managed in advance, and visitors may enter the route in sections rather than complete all nine kilometres.

SIX-STOP CULTURAL ROUTE: EVERY STOP DELIVERS PUBLIC EVIDENCE



Delivery sequence: evidence first, reversible pilots second, conditional works last

Confirm responsibility and evidence, then run a 90-day pilot; without upkeep records, do not expand



The concept does not invent a total investment figure. It uses cost packages and capped review. Each prototype separates survey and design, construction and components, digital equipment, staffing, maintenance, insurance, and site restoration. Permanent structures, basic public services, and safety roles cannot depend on one-off sponsorship. Professional estimates follow confirmed quantities, materials, utilities, and procurement.

Months 0-6 verify boundaries, ownership, heritage limits, trees, utility interfaces, fire access and accessibility. Months 6-18 install reversible pilots that avoid structural damage and record use, upkeep and complaints through at least one full season. Months 18-36 convert only the pilots that pass review into conditional works.

Each phase has stop rules: no permanent works before baseline evidence; no smart equipment before staffed fallback and upkeep funds; immediate shutdown when a pilot obstructs ordinary access, creates persistent disturbance or generates uncorrectable data risk. These rules enter procurement documents so delivery can learn and stop.

The first moves repair continuous access, open public ground-floor interfaces, install material bays and create staffed evidence displays. Landmark structures, permanent floor-area additions and expensive devices wait for the ledger to demonstrate real demand and trigger separate review.

Six work packages make the strategy procurable, reviewable and stoppable

Every package binds place, owner, acceptance evidence, upkeep resources and an exit condition

WP1 establishes facts: survey control, ownership and responsibility map, heritage and building audit, tree and utility checks, accessibility baseline, and a photographic record. WP2 repairs the civic minimum: crossings, continuous surfaces, shade, lighting, wayfinding, and staffed service points. WP3 installs the reversible spatial kit. WP4 runs the digital and AI trials. WP5 covers year-round staffing, maintenance, insurance, public communication, and restoration. Separating these packages prevents a software contract from absorbing basic construction and prevents a landscape image from concealing missing operations.

Acceptance occurs at four levels. A physical item must be safe, accessible, removable, and documented. A service must have hours, a duty roster, a human alternative, and a complaint route. A data or AI component must pass permission, security, bias, explanation, and shutdown review. An operating package must show maintenance labour, fixed cost, spare parts, and restoration funding. A package failing one level cannot be compensated by success at another.

The first 90-day pilot should occupy only one controllable Qinghe bay and one staffed AI Origin interface. It is deliberately smaller than the final image. The pilot answers whether the evidence card is understandable, whether maintainers can close faults, whether everyday passage survives a trial, and whether a first user will continue after novelty fades. Only a positive, documented review authorises the combined demonstrator and later extension to Dazhongsi.

ANALYSIS 12

Turn the strategy into six deliverable work packages

Every package has prerequisites, accountability, acceptance and stop rules

WP1

SITE EVIDENCE

survey, tenure, trees, movement and accessibility

PROCURE·ACCEPT·STOP

WP2

CONTINUITY

gaps, crossings, cycling and lighting

PROCURE·ACCEPT·STOP

WP3

KEY PROTOTYPES

reversible Qinghe, Origin and Dazhongsi samples

PROCURE·ACCEPT·STOP

WP4

AI+ SERVICES

health, education, commerce and human fallback

PROCURE·ACCEPT·STOP

WP5

CULTURE+ OPS

six-stop route, contribution wall and Open Week

PROCURE·ACCEPT·STOP

WP6

MAINTENANCE DATA

ledger, performance, review and exit

PROCURE·ACCEPT·STOP

Source: public call brief, agent taskbook and proposal working data; design-analysis basis only

JING-ZHANG ONE MILLIMETER

JUDGEMENT

Every package binds place, owner, acceptance evidence,

SPATIAL MOVE

Start with the smallest reversible move; expand only

PASS CONDITION

Ordinary space remains usable, ownership is named,

CENTENNIAL JING-ZHANG AI INNOVATION BELT OPEN CALL

26

Global Open Week is a year-round project production line, not a festival

Open problems, neighbourhood beta, Global Open Week and annual review form one seasonal loop




Q1 Problem Open Season completes G0 selection. Q2 District Beta Season completes bench tests and 30-day trials. Q3 JZ·1mm Global Open Week releases reusable components, runs maintainer sprints, and hosts bilingual public trials. Q4 AI City Public Review completes 90-day results, independent review, and the next year’s continue, revise, and stop list. A monthly maintainer clinic, quarterly public deliberation, and annual open ledger and safety drill create a stable rhythm outside large events.

A proposed “One Millimeter Commons” operating alliance has five roles. A steering committee sets public goals. A professional panel controls planning, heritage, safety, healthcare, education, privacy, and accessibility thresholds. A site team manages permits and duty. An open-source maintainer group controls versions. A public panel participates in trials, complaints, and annual review. Each project has one final accountable owner and an independent holder of stop authority.

ANALYSIS 13

The annual programme isa production line, nota festival

A four-season loop records needs, trials, Open Week and review in one evidence ledger



Source: public call brief, agent taskbook and proposal working data; design-analysis basis only

JING-ZHANG ONE MILLIMETER

The One-Millimetre Evidence Ledger records only verifiable, maintainable and reversible improvement

Success is not maximum footfall, but real use, professional review and maintained improvement

METRIC LAYERS: FACT, CONCEPT, OPERATION,

Do not turn provisional geometry, renderings, or concepts into performance claims

HIGH-CONFIDENCE FACT

- 43.6 sq km research
- 11.4 sq km overall design
- Three official key-area names and announced areas

CONCEPT RECOMPUTATION

- Provisional boundary ≈1,141.28 ha
- Concept green 18.35%
- Concept public space 11.66%

MEASURE AFTER DELIVERY

- 90-day maintenance acceptance
- Accessible-route availability
- Shade in high heat
- Complaint closure + takeover

MUST BE OBTAINED

- Official boundary + ownership
- Building, tree, utility surveys
- Thermal, drainage, cost, budget

The first 90 days establish a baseline. At day 365, operators, professional reviewers, and the public panel set next-year ranges. Complete task, standard, and design-depth indexes remain in structured matrices; the narrative explains the decisive judgments.

Metrics fall into three types to prevent concept numbers from being presented as performance. Fact metrics record announced areas and tasks. Geometry metrics recompute provisional layers to check zoning, continuity, and proportions. Operating metrics begin only after implementation, including shade availability during high-heat periods, accessible-route availability, handover time, valid work-order rate, components maintained for 90 days, and complaints closed on time.

The announced 11.4 sq km is a high-confidence textual condition. The provisional boundary recomputation of about 1,141.28 ha is only a consistency check. Concept green and public-space ratios, building footprints, and key-area geometry have low to medium confidence. Floor area ratio, height, statutory green ratio, tree quantity and health, thermal conditions, ordinary drainage capacity, and investment remain pending official data rather than receiving fabricated values.

JUDGEMENT

Success is not maximum footfall, but real use,

SPATIAL MOVE

Start with the smallest reversible move; expand only

PASS CONDITION

Ordinary space remains usable, ownership is named,