


This proposal designs the Centennial Jing-Zhang AI Innovation Belt as a continuously operating, publicly auditable urban proving corridor. Its replicable smallest unit is the validation unit, made of four parts: a spatial host, a validation protocol, a public disclosure board and an exit mechanism. Nine segments and five bands along the Jing-Zhang Heritage Park link Zhongzhiyuan, the AI Origin Community and Dazhongsi, supplied by the Zhongguancun service wing and the Xiaoyue River scenario wing.

Core loop: propose → validate → disclose → convert

Three hard constraints


- Failure must be disclosed: projects that fail validation, and the reasons why, enter the same public board as the successes.
- The human fallback must not be slower or costlier: every AI service keeps a staffed channel, and choosing it must carry no penalty in time or fee.
- Opt-in by default: data capture and intelligent services in public space are off until the user actively joins.

The validation unit: four parts



Three-Level Scope and Evidence Chain Overview

Coordinated research area approx. 43.6 km² | Overall design area approx. 11.4 km² | Key detailed design area approx. 368.4 ha



All extents are organiser-registered provisional rough substitutes with official_boundary=false, geometry_role=provisional_constraint and boundary_precision=provisional_rough. The announcement publishes no precise red-line drawing or GIS dataset, so this figure is not an approval basis, a tenure conclusion or a precise-area reference. Areas are recomputed in EPSG:4548 and cross-checked against the announced approximate values. Data: geometry/site_boundary.geojson, geometry/key_areas.geojson, geometry/constraints.geojson.

Evidence chain



Declared gaps

- Official precise red line: not published
- FAR ceiling: not published
- Height ceiling: not published
- Density ceiling: not published
- Green ratio floor: not published
- Setback control: not published
- Official control indicators available = 0

Scope tiers

Coordinated research area	approx. 43.6 km²
background, research judgement only	
Overall design area	approx. 11.4 km²
regulatory-depth urban design, main scope	
Key detailed design area	approx. 368.4 ha
three key areas, detailed design depth	
Zhongzhiyuan acceleration area	approx. 192.1 ha
full-stack innovation, pilot production	
Beijing AI Origin Community	approx. 104.3 ha
living scenarios, public participation	
Dazhongsi industry cluster	approx. 72.0 ha
intelligence-native consumption, interchange	

Three-level scope and evidence chain

research approx. 43.6 km² overall design approx. 11.4 km² key detail approx. 368.4 ha

Why a proving corridor rather than one more demonstration park

- 01 A demonstration shows results that already succeeded; validation opens the process while it happens, failures included.
- 02 A park gathers firms behind a boundary; a corridor admits proposals through a protocol, and its space is open to anyone who signs one.
- 03 Demonstration facilities often idle once the showcase ends; a validation unit has an exit mechanism and releases its space on failure.
- 04 A demonstration benefits the firms that were selected; validation benefits everyone who can read the disclosure board.

Twelve AI scenario nodes

SCN-01 Dazhongsi intelligence-native consumption district Intelligence-native consumption	SCN-04 Xueyuan Road open science-education interface Campus-city shared validation	SCN-07 Origin talent community smart living services Smart living in the community	SCN-10 Inclusive fitness and barrier-free mobility Inclusive fitness and accessibility
SCN-02 Dazhongsi station first-and-last-mile interchange Low-speed autonomous interchange	SCN-05 AI + health validation campus Clinical decision support validation	SCN-08 Jing-Zhang heritage AI interpretation Cultural narrative interpretation	SCN-11 Zhongzhiyuan proving plaza and compute open day Open compute and model validation
SCN-03 Beixiaguan community AI care station AI + community care	SCN-06 AI Origin proving plaza Public proposal and disclosure	SCN-09 Xiaoyue River waterfront delivery-robot validation Delivery robots	SCN-12 Zhongzhiyuan pilot production and governance review Governance agent review

- flagged as an industry validation scenario (4 in total)
- Points are indicative and express no siting conclusion. Each node registers its beneficiary profile, data boundary and human fallback route.

Three key detailed design areas

Zhongzhiyuan AI Acceleration Area	approx. 192.1 ha
Full-stack innovation and pilot production: compute open days, model validation, governance agent reviews.	
Beijing AI Origin Community	approx. 104.3 ha
Living scenarios and public participation: the proposal plaza, community care, smart living services and the main disclosure board.	
Dazhongsi AI Industry Cluster	approx. 72.0 ha
Intelligence-native consumption and interchange validation: first-and-last-mile low-speed autonomy, consumption district scenarios.	


Spatial skeleton: nine segments, five bands

Nine longitudinal segments (south to north)	Five transverse bands (west to east)
B1 Dazhongsi south gateway	W2 Zhongguancun tech-service wing interface
B2 Dazhongsi AI industry core	W1 Western innovation band
B3 Beixiaguan stitching	S Jing-Zhang Heritage Park proving spine
B4 Xueyuan Rd science-education	E1 Eastern innovation band
B5 Origin Community south interface	E2 Xiaoyue River scenario-enabling wing interface
B6 Beijing AI Origin Community core	
B7 Xiaoyue River scenario-enabling	
B8 Zhongzhiyuan validation core	
B9 Zhongzhiyuan pilot and compute	

Nine segments and five bands break the strip site into 45 seamless, non-overlapping cells, the shared base for all land-use, metric and phasing calculations.

Land-Use Structure · Nine Segments and Five Bands


Overall design area approx. 11.4 km²; 45 seamless non-overlapping cells | EPSG:4326 exchange, EPSG:4548 area recalculation



Conceptual proposal only. Partition lines express no road red line, no parcel tenure and no approval conclusion. The base extent is the organiser-registered provisional rough boundary official_boundary=false; every layer and metric must be recalculated as a whole once the official precise red line is published. Land-use codes follow the national land and sea use classification guideline. The three equal-scale panels show the same corridor in sequence, B1 to B9 from south to north. Data: geometry/land_use.geojson, geometry/roads.geojson, geometry/site_boundary.geojson.

Figure 3 Key areas, validation units and AI scenario nodes

Centennial Jing-Zhang AI Innovation Belt - Urban Proving Corridor - conceptual proposal




Boundaries are provisional rough surrogate extents inferred from public information (official_boundary=false, geometry_role=provisional, constraint). They do not represent official red lines, approval outcomes or implementation commitments. Areas and lengths are computed in EPSG:4548; exchange coordinates are EPSG:4326 (longitude, latitude). The confidence column shows W/M/L. Building-related metrics rest on assumed site coverage and average storeys and are indicative, not regulatory plan conclusions. Extents are provisional rough surrogates (official_boundary=false).

Key areas and AI scenarios

Figure 4 Mobility and blue-green public space structure



Centennial Jing-Zhang AI Innovation Belt - Urban Proving Corridor - conceptual proposal



Alignments and green space are conceptual suggestions and do not express road red lines, cross-section design or ownership boundaries. Lengths are computed in EPSG:4548; exchange coordinates are EPSG:4326. Data: geometry/roads.geojson, geometry/green_space.geojson, geometry/public_space.geojson, metrics.json. Extents are provisional rough surrogates (official_boundary=false) and must be fully recomputed once official precise boundaries are published.

Figure 5 Core metrics, phasing and evidence chain

Centennial Jing-Zhang AI Innovation Belt - Urban Proving Corridor - conceptual proposal



Metric definitions are in metrics.json; areas and lengths are computed in EPSG:4548 (CGCS2000 3-degree zone, central meridian 117 E); exchange coordinates are EPSG:4326 (longitude, latitude). The confidence column shows W/M/L. Building-related metrics rest on assumed site coverage and average storeys and are indicative, not regulatory plan conclusions. Extents are provisional rough surrogates (official_boundary=false).

Core metrics, phasing and evidence chain

Core metrics

Overall design area	11,412,825 m ²
Green ratio	29.41 %
Public space share	11.35 %
R&D land area	2,008,878 m ²
Reserved land area	416,693 m ²
Proving spine length	9,722.3 m
East-west stitches	7
AI scenario nodes	12
Industry validation scenarios	4
Key areas	3
Phase 1 area	3,169,220 m ²
Official controls available	0

Three kinds of metric

- 01 Recomputable geometry metrics: independently recalculable from geometry/ in the same CRS, with identical results for any third party.
- 02 Assumption-derived metrics such as building scale: confidence is bounded by the assumption, and each entry carries a caveat and assumption id.
- 03 Declared-gap metrics such as the count of available official controls, which is 0: their purpose is to keep the gap visible rather than fill it.

Key assumptions

- A-BOUNDARY-001 All areas rest on provisional rough extents; recompute once the official red line is published.
- A-COVERAGE-001 Footprints come from assumed site coverage; neither a survey nor a regulatory conclusion.
- A-MOBILITY-001 Alignments are conceptual; rail crossings need railway and municipal development.
- A-CONTROLS-001 The five official controls are missing; no back-calculation is attempted.

Compliance premise: gaps in official planning controls

No precise red line, GIS dataset or control indicator is published for this project. Every spatial and quantitative conclusion rests on the organiser-registered provisional rough surrogate extents (official_boundary=false, geometry_role=provisional_constraint). They are conceptual suggestions and are not regulatory-plan conclusions, approval outcomes, tenure conclusions or implementation commitments. Full recomputation is required once official boundaries and controls are published.

Phasing plan and measurable indicators

- Phase 1 · proving cores 2026–2028 27.77 %
One proving plaza and one spine sample segment in each of Dazhongsi, the AI Origin Community and Zhongzhiyuan, closing the propose-validate-disclose-convert loop.
3 validation units built; at least 30 projects disclosed in total; 100 % of failures disclosed.
- Phase 2 · spine and stitches 2029–2031 40.62 %
Complete the north-south spine, deliver the Xiaoyue River scenario wing and the seven east-west stitches, removing the detours caused by the rail corridor.
Spine continuous end to end; 7 stitches built; continuous barrier-free surface along the whole belt.
- Phase 3 · conversion to operation 2032–2035 31.61 %
Stitch the Xueyuan Road education cluster and the Beixiaguan area, and shift validation from project mode into standing operation with the conversion channel institutionalised.
The conversion rate of validated results into procurement or standards is publicly reportable; the operator runs on a standing basis.

Three institutional devices

- Validation protocol
Before deployment each validation unit must sign a public protocol stating the scope of data capture, the retention period, the exit route and the accountable party. The protocol itself is public.
- Failure disclosure
Failures, suspensions and takeovers must be disclosed on the same board as the successes, with no selective release. Only recorded failure spares the next team from paying for it again.
- Conversion channel
Validated results need a defined route into adoption: a procurement catalogue, a local or association standard, or a published technical guideline. Without it, validation is only a demonstration.

Standards, laws and policies applied

- Official notice 1.3 / 1.4 / 1.5
purpose, three-level scope, tasks and required depth
- Open-call task book
positioning, functions, three areas and two wings, six tasks, boundary clauses
- Urban design administrative measures
implement planning, guide architecture, coordinate public space and massing
- Regulatory detailed planning measures
separate known controls, design suggestions and items pending confirmation
- Land and sea use classification guideline
one classification logic, no invented categories
- Generative AI interim measures
lawful data sources, content safety, user rights
- Barrier-free Environment Construction Law
accessibility of movement, services and information
- Elderly-friendly smart technology plan
retain conventional service routes and staffed channels
- Architectural design depth provisions
urban design level only; architectural design depth not entered (not applicable)

Mandatory items carry a solid mark; the rest are referenced or not applicable. The full mapping is in standard_matrix.json.

Task coverage

- Industry and future-city research
Spatial demand of the full-stack AI chain
- Renewal and regulatory-depth urban design
Nine-segment partition, mobility, blue-green, character
- Detailed design of key areas
Three key areas and their validation units
- AI ecosystem, talent and AI+ scenarios
12 nodes, beneficiary profiles, data boundaries
- Project list, policy and phasing
Three-tier list, three devices, three phases
- Metric system and compliance
25 metrics, recomputation, matrix, declared gaps
- Evidence inventory in this package

- 23 compliance_matrix.json
requirements mapped one by one
- 9 standard_matrix.json
standards, laws and policies cited
- 15 design_depth_matrix.json
design-depth items with sections and layers
- 25 metrics.json
metrics: 23 known, 2 declared gaps
- 9 geometry/"_geojson
layers, EPSG:4326 exchange, EPSG:4548 recalculation
- 5 assets/figures/"_png
figures, one set per language

Boundaries of use

- Every spatial and quantitative conclusion in this booklet is a conceptual suggestion for further study by professional teams.
- It is not a regulatory-plan conclusion, an approval basis, a tenure boundary, a construction commitment or a fiscal commitment.
- No non-public, internal or classified data is used, no personal data is used, and no company list, investment figure or output value is invented.
- Once official boundaries and controls are published, the package must be recomputed as a whole on the same definitions, not patched locally.

Conceptual suggestion · for further study by professional teams · not an official approval or implementation commitment