


43.6 KM² IS A CITY NETWORK, NOT ONE LANDSCAPE STRIP

Longitudinal Jingzhang public framework × eight real cross-streets × Qinghe-Xiaoyue × western service wing; grey dashed line is provisional.



JINGZHANG CROSS-STREETS

Eight real cross-city streets for a 43.6 km² innovation district

Innovation already exists on both sides of the railway. The design task is to cross between campuses, neighbourhoods, stations, productive ground floors, and two rivers.

43.6 km ²	COORDINATED RESEARCH
resources, mobility, industry, blue-green network	
11.4 km ²	OVERALL DESIGN
land use, cross-streets, blocks, public ground	
368.4 ha	THREE KEY AREAS
front/back of house, station, sections, first projects	


THREE POSITIONS IN ONE SPATIAL SYSTEM

- 01 Centennial Jingzhang Cultural Belt
- 02 Urban AI Life Experience Belt
- 03 AI Convergent Innovation Belt

FIVE FUNCTIONS: FULL STACK / ECOSYSTEM / AI+ SCENARIOS / LIVELY CITY / GOVERNANCE RULES

11.4 KM² CONCEPT LAND USE
NO BLANK CANVAS

Complete topology expresses functional mix; not a survey, statutory zoning, or property right.



FIVE CITY MATERIALS

- R&D / INCUBATION
0802
- UNIVERSITY / RESEARCH
0604
- HOUSING / COMMUNITY
0701,0702
- COMMERCE / SERVICE / CULTURE
05/0803
- PARK / ECOLOGY
1401,1402
- CROSS-STREET / PUBLIC NODE
1207,1403

FOUR GROUND-FLOOR ACTIONS

- 01 retain
- 02 adapt ground floor
- 03 partnership lease
- 04 conditional infill

WATERFRONT RESEARCH: COMPLETE GRADIENT FROM RIVER TO SECURE R&D

STUDY RANGE: habitat 12-20 m | clear walk ≥3 m | storm 6-12 m | forecourt 8-15 m



NEAR-CAMPUS TRANSFER: A FIVE-MINUTE CAMPUS-TO-COMPANY CHAIN

STUDY MINIMA: clear walk ≥3 m | one-way cycle ≥2.5 m | workroom 6-9 m | entries ≥2/100 m



FOUR-QUADRANT STATION: SURFACE FIRST; TEST BRIDGE OR UNDERGROUND LATER

STUDY MINIMA: arrival ≥12×20 m/corner | crossing ≤2 signal stages | 150-300 cycles/corner to verify




Status 2026-08-10 | Concept urban design. Provisional geometry and OSM are for study only, not statutory, ownership, or engineering evidence.

FIG 02 / 05


THE LONGITUDINAL PARK EXISTS; DESIGN THE CROSSINGS AND COMPLETE SECTIONS

Eight streets follow real waterways or roads; each must reach ground floors, stations, campuses, or neighbourhoods beyond the park edge.




WATERFRONT RESEARCH: COMPLETE GRADIENT FROM RIVER TO SECURE R&D

STUDY RANGE: habitat 12-20 m | clear walk ≥3 m | storm 6-12 m | forecourt 8-15 m



NEAR-CAMPUS TRANSFER: A FIVE-MINUTE CAMPUS-TO-COMPANY CHAIN

STUDY MINIMA: clear walk ≥3 m | one-way cycle ≥2.5 m | workroom 6-9 m | entries ≥2/100 m



FOUR-QUADRANT STATION: SURFACE FIRST; TEST BRIDGE OR UNDERGROUND LATER

STUDY MINIMA: arrival ≥12×20 m/corner | crossing ≤2 signal stages | 150-300 cycles/corner to verify



Status 2026-08-10 | Concept urban design. Provisional geometry and OSM are for study only, not statutory, ownership, or engineering evidence.

FIG 04 / 05

THREE KEY AREAS: THREE BLOCK TYPES, NOT THREE ISOLATED OBJECTS

Working windows use OSM building context; colour marks ground-floor adaptation, red is conditional infill, and lines are public paths.

Waterfront Research Blocks

01 Zhongzhiyuan AI Autonomous Innovation Acceleration Area

Qinghe Prototype Court

GROUND-FLOOR PLAN

One public line links Xuezhiyuan Station, the estate's open ground floors, and the Qinghe walk; secure R&D is served independently from an estate service road.

CONCEPT SECTION

Habitat buffer 12-20 m, accessible clear width at least 3 m, storm terrace 6-12 m, and public forecourt 8-15 m; all are study ranges pending survey.

CONTRIBUTION SHELF

6-12 rotating bays: standards, open tools, and access improvements; no R&D data or ads.

Near-Campus Transfer Blocks

02 Beijing AI Origin Community

Hundred-Table Review Hall

GROUND-FLOOR PLAN

A five-minute chain connects campus gate, small workrooms, Hundred-Table Hall, Origin Building, and Starlight Avenue ground floors, with a night route to housing and food.

CONCEPT SECTION

Walking clear width at least 3 m, one-way cycle band at least 2.5 m, ground-floor depth 6-9 m, review module about 9×18 m, and at least two public doors per 100 m; all are study targets.

CONTRIBUTION SHELF

Open tools, peer review, and community solutions; optional individual or team credit.

Four-Quadrant Station Blocks

03 Dazhongsi AI Industry Cluster

Dazhongsi Four-Corner Commons

GROUND-FLOOR PLAN

Surface crossings and accessible vertical routes first create one arrival ground across four station corners; content making, repair/returns, night school, and civic service occupy the four ground floors.

CONCEPT SECTION


Each corner studies an arrival ground at least 12×20 m, surface crossing within two signal stages, 150-300 cycle spaces subject to demand, and an accessible vertical route on both rail sides.

CONTRIBUTION SHELF

Repair, access, rights, and material reuse; judge public service, never sales.

ONE LEDGER FOR DESIGN, DATA LIMITS, AND DELIVERY AUTHORITY

Known is not statutory; a target is not a baseline; unknown does not mean design stops.



STOP CONDITIONS

No official geometry and engineering data: do not lock FAR, height, demolition, bridge/tunnel, or capex. No lease and maintenance duty: do not claim open ground floor. No human alternative: do not operate AI scenarios.

Status 2026-08-10 | Concept urban design. Provisional geometry and OSM are for study only, not statutory, ownership, or engineering evidence.

FIG 05 / 05

INTERNATIONAL CONVERSION: bilingual outreach → visit → peer review → bounded test → service/equipment → desk or short lease → long lease/research partnership; no investment, funding, policy, or approval promise.

EIGHT GATES: open call → rights/privacy/safety screening → room/operator match → bounded sandbox → human go/no-go → limited public use → evaluation → stop/repeat/convert

