


JINGZHANG · 1909 — 2026

JINGZHANG START LINE

AI SPORTS & WELLNESS VITALITY BELT

From the century-old railway origin to a global AI sports & wellness vitality belt
A century ago China's railway set off from here; today, let the world start running from here.



Concept: the world's first AI × Sports & Wellness Vitality City Laboratory

Submission: nixiankaide1 (Chenyuan Z) · Generated by Agent: Hermes · 2026 International Open Call for Urban Design

One Corridor · Two Wings · Three Starts · Five Nodes · 22 km START LINE corridor concept · three-level scope · provisional boundary (concept until recalculation)

All spatial content in this booklet is a conceptual recommendation / reference for professional teams; boundaries are provisional (not an official planning boundary)

01

Design Basis and Sources

Announcement, taskbook, public site package, professional standards and provisional-boundary disclosure

02

Three-Level Scope

Coordinated Research 43.6 km2 / Overall Design 11.4 km2 / Key-Area Detailed Design 368.4 ha

03

Overall Concept and Spatial Structure

START LINE naming system · One Corridor, Two Wings, Three Starts, Five Nodes · Logo direction

04

Land Use and Function

44 zones · Research 34% + Sports 6% dual signature · Demolish - Renovate - Retain

05

Transport, Municipal and Blue-Green

One vertical three horizontals · 22 km START LINE corridor · rail connections · green network and public-space library

06

Three Key Areas

Zhongzhiyuan Verify Start · AI Origin Origin Start · Dazhongsi Experience Start

07

Renewal Projects and Phasing

10 catalyst projects · PH-1/2/3 three-phase implementation · event operation system

08

Metrics and Compliance

Core metrics table · recalculation method · 23 mandatory announcement items fully covered

09

Risks and Pending Materials

provisional-boundary limits · regulatory-plan pending items · copyright and AI-generation responsibility



Primary Authority

- The 'Prequalification Announcement of the International Open Call for Urban Design of the Centennial Jing-Zhang AI Innovation Belt' (2026-05-09, Haidian Branch of the Beijing Municipal Commission of Planning and Natural Resources) establishes the three-level scope, the three key areas and the deliverable depth [source:OFFICIAL-ANNOUNCEMENT]
- The open-call taskbook for global agents: ten agent co-creation principles, three positioning statements, five functions, Three Zones Two Wings, six agent tasks and the unified boundary clause [source:AGENT-TASKBOOK]

Material Tiers

- Repository site package brief/site-package/: design_brief, allowed_design_space, agent_taskbook, sources, visual_style_recommendations [source:SITE-PACKAGE]
- Public-source registry data/source_registry.json: determines usable_for_formal status per source [source:SOURCE-REGISTRY]
- Processed fact pack data/processed/agent_fact_pack.md: navigation layer whose conclusions trace back to original source_id

Professional Standards

- MOHURD Urban Design Administrative Measures: coordinating building layout, landscape character, public space and urban identity
- MOHURD Regulatory Detailed Planning Compilation/Approval Measures: distinguishing known controls / design recommendations / items to be confirmed
- MNR Land-Use and Sea-Use Classification Guide: unified land-use classification semantics [standard:MNR-LAND-USE-CLASSIFICATION-GUIDE]

Boundary Disclosure

- The official precise red line and official key-area polygons are not yet available; provisional_boundaries.geojson is used (geometry_role=provisional_constraint, official_boundary=false)
- All areas/ratios/scales are conceptual recommendations; the full package is recalculated after the official polygon is released [source:BOUNDARY-SOURCE][source:KEY-AREA-SOURCE]
- Material gaps: official red line, regulatory indicators, current building stock, ownership, engineering conditions — see the risks chapter

Coordinated Research Area

43.6 km²

- North to North 5th Ring Road
 - East to Jingzang Expressway
 - South to Xizhimen Outer Street
 - West to Wanchang Road
- Industrial strategy and future urban-form research — 'what is the belt, where is it going'

Strategy and conceptual research: naming system, case translation, future urban form

Overall Design Area

11.4 km²

- North to North 5th Ring Road
 - East to Xueyuan Road, Xitucheng Road, etc.
 - South to Xizhimen Outer Street
 - West to Datongmen East Road, Heqing Road, etc.
- Urban renewal and regulatory plan-depth urban design — 'how do the cores and the belt work together'

Spatial structure, land-use layout, transport/rail/municipal, blue-green system, character control

Key-Area Detailed Design Area

368.4 ha

- Zhongzhiyuan AI Independent Innovation Acceleration Area
 - Beijing AI Origin Community
 - Dazhousi AI Industry Cluster
- Detailed design of the three key areas — 'how do the cores work together'
- Detailed mini-schemes for the three areas, Demolish-Renovate-Retain concepts, project handles

Three-Level Transmission Logic

- The Coordinated Research layer establishes the 'AI × sports & wellness' proposition and the 'START LINE' naming system, constraining the 'One Corridor, Two Wings, Three Starts, Five Nodes' structure of the Overall Design layer
- The Overall Design layer implements the structure as land-use ratios, a transport skeleton and a public-space network; the Key-Area layer delivers perceivable spatial schemes and project handles within the three 'Start' cores
- The announcement's textual limits and areas (43.6 / 11.4 / 368.4) are the formal task basis; derived drawings and metrics reflect design intent only, and once the official polygon is in place, site_boundary / land_use / key_areas / buildings / roads / phasing and all area-type metrics must be recalculated

Three Meanings United in the Start Line

- Railway origin: Tsinghuayuan Station is the zero-kilometer point of the Jing–Zhang Railway and the start of China's self-built railways (1909 independent innovation)
- Sports origin: sports & wellness is humanity's first language; the start line belongs to everyone (2026 city-scale sports laboratory)
- Innovation origin: AI computing signals make the city perceivable, responsive and evolvable — the start line of global AI innovation

Spatial Structure: 'One Corridor, Two Wings, Three Starts, Five Nodes'

One Corridor Jing-Zhang Heritage Park green START LINE corridor: 22 km sports & wellness composite corridor (running + cycling + walking three-line)


Two Wings West = research-innovation belt (Xueyuan Road university cluster + research institutes); East belt = living-experience belt (urban AI life experience)

Three Starts Zhongzhiyuan (Verify Start) • AI Origin (Origin Start • Tsinghuayuan zero-kilometer) • Dazhongsi i (Experience Start)


Five Nodes Sports Park (north) • Tsinghuayuan Start Plaza (north-central) • Xueyuan Road Vitality Station (central) • Xiaoyue River waterfront belt (west wing) • Xizhimen gateway (south)

Synergy Loop

- Verify Start outputs → Origin Start incubation → Experience Start launch → the two wings supply factors (capital/scenarios) → data flows back to Zhongzhiyuan for re-validation
- Logo direction: start-line gate + three running-track arcs (rail black / pulse red / computing blue) + 1909—2026 time scale; four-color system




Land-Use Recalculation (land_use.geojson, 44 zones without gaps)



Four Demolish - Renovate - Retain Logics (conceptual)

- Retain**—Zhang railway heritage and heritage-protection units (former Tsinghuayuan Station site, etc.)
: authentic protection; no new construction within heritage control areas
- Renovate**—Industrial land and stock around universities: functional conversion + spatial mending
- Demolish**—Dilapidated buildings and inefficient land: possibilities raised only at the conceptual level, confirmed after building-by-building review
- New Node**—Complexes at the Three Starts: supplementing testing/validation and experience/display functions



One Vertical, Three Horizontals

- One Vertical - JINGZHANG main-line slow-mobility composite corridor (START LINE corridor R-007): running + cycling + walking three-line, 22 km concept / approx. 9.7 km measured in the provisional range
- Three Horizontal - Xueyuan Road, Dazhongsi East Road, Xizhimen Outer Street: east-west distribution and rail connections; intersections are the scenario nodes
- Rail Line 13, Changping Line and the Zhichun Road—Xizhimen interchange anchor (conceptual); TOD around the Three Starts stations, 'start running right after exiting the station'

Blue-Green Public Space

- Qinghe (north) — Xiaoyue River (west wing) — Heritage Park green corridor (main axis) connected; parks and green space + squares arranged along the movement line
- Green-network value: continuity over single-point scale; Green 12% + Plaza 4% form the blue-green public-space network
- Public-space component library: fitness-assessment station, supply station, start gate, zero-kilometer post, honor wall, pace signage — six modules
- Four pilgrimage landmarks: L1 zero-kilometer post / L2 open-source achievement kilometer corridor / L3 AI Sports Laboratory / L4 Zhongzhiyuan Verification Tower

Municipal and New Infrastructure (conceptual)

- Edge computing (fitness-assessment stations / pace-terminal edge nodes) + sports & wellness data nodes + distributed energy (photovoltaic running surfaces, storage)
- Traditional municipal pipelines and new facilities share trenches to reduce re-excavation; municipal facilities participate in scenario generation (manhole-cover nameplates, distribution-box data art)



Composite system of transport / slow mobility and blue-green public space (mobility-bluegreen)

Zhongzhiyuan ▪ Verify Start

192.1 ha

- Positioning: Full-Stack Independent AI Innovation Acceleration Area; run innovation outcomes through real scenarios
- Structure: 'One Core, One Ring, One Belt' — Verification Tower + testing/validation cluster, industry-service ring, sports & wellness testing belt facing the Qinghe River
- Buildings: mainly renovating existing research buildings, with a new Verification Tower at the core (industry landmark, data-visualization media facade)
- Scenarios: SC-08 esports × physical-training, TV-01 exercise-prescription validation ground, TV-03 health data sandbox
- Risks: privacy boundaries and Human Review precede construction; plot-by-plot ownership confirmation for stock renovation

AI Origin ▪ Origin Start

104.3 ha

- Positioning: composite carrier of the world-class AI innovation ecosystem and the Jing-Zhang Railway zero-kilometer memory
- Structure: 'One Plaza, One Axis, One Corridor' — Tsinghuayuan Start Plaza (zero-kilometer post + start gate), Xueyuan Road Innovation Axis, Heritage Park main corridor
- Buildings: heritage-preservation display of the former Tsinghuayuan Station site, renovation and mending around it, transparent view corridor to the zero-kilometer post
- Scenarios: SC-05 university sports data bridge, SC-09 AI cultural guide start
- Risks: heritage redline is the highest constraint; station-integration interface coordination; honor-wall content review mechanism


Dazhongsi ▪ Experience Start

72.0 ha

- Positioning: southern gateway of AI industry agglomeration and life experience, low-threshold use-and-go
- Structure: 'One Core, Two Interfaces' — Dazhongsi Vitality Core (smart-court flagship + fitness-assessment experience center), community interface, rail interface
- Buildings: mainly new node complexes + street-level commercial interface renewal, controlled massing and setbacks, southern-gateway sense of arrival
- Scenarios: SC-03 smart court, SC-04 exercise-prescription block, TV-02 smart-court algorithm validation ground, SC-12 large-event crowd management
- Risks: renewal sequencing matched with property-rights negotiation; event emergency evacuation and security; human final arbitration for foul calls

Three areas total 368.4 ha, forming the 'verify—origin—experience' spatial movement line

- All three polygons are provisional; after the official polygon is in place, boundaries and areas are recalculated, corresponding to metric key_area_count=3
- Each area reaches the urban-design depth of an integrated planning implementation plan (plot-level land use, intensity and public-space control)



Renewal Project List (10 core catalysts)

#	Project	Type	Location	Phase
1	START LINE corridor connection project	Blue-green / slow mobility	Heritage Park main corridor	PH-1
2	Zero-kilometer plaza	Public space	AI Origin	PH-1
3	Smart court	Sports facility	Dazhongsi Vitality Core	PH-1
4	Verification Tower	Industry landmark	Zhongzhiyuan core	PH-1
5	Fitness-assessment station network	New infrastructure	Five Nodes + belt-wide	PH-2
6	Qinghe Sports Park	Blue-green	Northern Qinghe waterfront belt	PH-2
7	Xueyuan Road Vitality Station	Public space	Xueyuan Road	PH-2
8	Data sandbox center	Governance facility	Zhongzhiyuan / AI Origin	PH-2
9	Event operations base	Sports operations	Dazhongsi	PH-2
10	Exercise-prescription block	Community renewal	Dazhongsi community interface	PH-3

Three-Phase Implementation

- PH-1 Near term 2026—2028

Catalyst projects at the Three Starts: start-line plaza, smart court, Verification Tower — establishing a perceptible 'verify—origin—experience' prototype
- PH-2 Mid term 2028—2030

Completion of the 22 km START LINE corridor + fitness-assessment station network — realizing the 'runnable city' skeleton
- PH-3 Long term 2030—2035

Belt-wide ecological operations: scenario access network and annual event system maturing

Operation Mechanism and Event System (conceptual)

- Annual events: Jing-Zhang AI Marathon (April) • Global Developer Sports Week (June) • AI × Sports Industry Summit (September) • Open-Source Annual Exhibition + Pulse Medal Awards (November)
- Developer community: weekly 'hacker runs' (running + code review) • application-based scenario-access sandbox • Data-Compliance Human Review Committee
- Conversion path: events → developer community → scenario sandbox → enterprise landing → policy-resource matching

Core Metrics (same source as metrics.json)


site_area_sqm	11,412,825 m ²	Overall Design Area (provisional recalculation)
green_ratio	14.07%	Green area / overall area
public_space_ratio	6.80%	Plaza + public space / overall area
building_footprint_area_sqm	3,297,093 m ²	Sum of building footprint areas
sports_facility_ratio	5.62%	Sports land 0805 share — signature metric
trail_length_km	9.7 km	Measurable length of START LINE corridor R-007 in the provisional range (22 km belt-wide concept)
research_space_ratio	33.73%	Research land 0802 share
residential_ratio	21.72%	Residential land 0701 share
commercial_ratio	5.98%	Commercial & services land 05 share
green_blue_ratio	15.25%	Park green space + plaza share
building_count	311	Number of conceptual building footprints
land_use_zone_count	44	Number of land-use zones
key_area_count / phase_count	3 / 3	Key areas / implementation phases
scenario_card_count	12	Scenario cards (incl. 3 testing/validation)
persona_count / landmark_count	6 / 4	Personas / pilgrimage landmarks
case_study_count / renewal_project_count	6 / 10	Global cases / core catalyst projects

Risks and Pending Materials

- Alignment boundary** temporary rough boundary; it cannot serve as an official planning boundary / approval / precise-area basis; after the official polygon is released, all layers and area-type metrics must be recalculated
- Regulation and planning heighting** FAR and building height limits per plot, road red lines, plot boundaries, heritage control lines, municipal pipelines and traffic sections — all listed as items to be confirmed
- Current building stock**, ownership, engineering conditions; Demolish-Renovate-Retain is raised only at the conceptual level
- AI-generated recommendations** are conceptual recommendations / reference schemes for professional teams to develop; they do not replace formal planning and do not constitute government-approved conclusions; names, Logo, landmarks and events are conceptual directions, not approved construction
- Message control** at the former Tsinghuayuan Station site, health-data compliance and event safety must be reviewed by the relevant professional bodies

Compliance Coverage

- Announcement 1.3/1.4/1.5 all items — covered
- agent.1 — agent.6 six agent tasks — covered
- Five mandatory standards — addressed
- 15 core depth items — complete
- 12 scenario cards (incl. 3 testing) — satisfied
- 6 personas · 4 landmarks · 6 cases — satisfied
- 10 renewal projects · 3 phases — satisfied
- Recalculation: EPSG:4548 projection, GeoJSON exchange EPSG:4326
- floor_area_ratio = unknown (regulatory plan not released, not fabricated)



Core metrics recalculation and evidence chain (metrics-evidence)