

AI does two very physical things to a city: it makes heat, and it needs to be near. This proposal turns both into spatial rules — waste heat is returned to public space, compute comes down to street level, and the switch that stops it stays in human hands.

Fig.1 Overall spatial structure: THE WARM LINE

One spine · 13 compute watering stations · 13 east-west stitching links · three areas, two wings

SITE OVERVIEW

Concept proposal · not statutory planning · provisional boundary
zww1992 / jingzhang-warm-line



Design position

AI does two very physical things to a city: it makes heat, and it needs to be near. This proposal turns both into spatial rules — waste heat is returned to public space, compute comes down to street level, and the switch that stops it stays in human hands.

Two wings



Three areas, two wings: compute down → scenarios opened → resources allocated → human dispatch and review

Three scope levels

- 43.6 km² Coordinated research area
- 11.4 km² Overall design area
- 368.4 ha Key detailed-design areas

Legend

- Warm Line spine (heritage-park slow line)
- Compute Watering Station (edge compute + public waste heat)
- AI pilgrimage landmark
- Park green / buffer green
- Key area (provisional extent)
- Overall design area (provisional boundary)

Naming system: from steam-era resupply to agent-era resupply

Proposal term	Jing-Zhang prototype	Spatial content
Compute Watering Station	Water station	Edge compute + charging + public waste heat + services
Dispatch Hall	Dispatch office	A public task queue with a human stop lever
Marshalling Yard	Marshalling yard	Assembling, running and reviewing test scenarios
Stitching Link	Level crossing	Pedestrian-priority east-west link and scenario interface
Milestone	Mileage marker	Honour display and contributor record along the line


The base is a provisional rough boundary inferred from the announcement's written extents (provisional constraint, official_boundary=false). It supports concept generation, display and self-check only; it is not an official redline, an approval basis or a precise-area basis. All spatial ideas are concept suggestions for professional teams to develop. Areas are recomputed in EPSG:4548; see sources.json.

Fig.2 Land-use structure and the three scope levels

Concept land-use structure over the provisional boundary (not a statutory land-use plan)

LAND USE

Concept proposal · not statutory planning · provisional boundary
zww1992 / jingzhang-warm-line



Land-use composition (recomputed, hectares)

1401 Park green	178.1
0802 R&D	155.4
0702 Community service	139.7
0701 Residential	138.2
1207 Road	116.0
0804 Education	109.4
05 Commercial	100.5
0805 Sports	71.3
1402 Buffer green	47.1
16 Reserved (compute & heat)	41.7
1403 Civic square	20.0
0806 Health care	14.6
0803 Culture	9.3

Total equals the site area: no gaps, no overlaps 1,141.3

Three scope levels

- 43.6 km² Coordinated research area: ecosystem and future urban form
- 11.4 km² Overall design area: the extent of this land-use concept
- 368.4 ha Key areas: three detailed-design districts

Structure logic: one partition built from four subtractions

- 1 Road land**
Streets and stitching links are subtracted first to give a readable block skeleton
- 2 Station squares**
Forecourts are subtracted at the 13 links, so public space precedes buildings
- 3 Green spine**
The continuous park and station gardens follow the heritage slow line
- 4 Buffer green**
A protective strip is subtracted along the eastern traffic edge
- 5 Remaining blocks**
What is left is coded by the three-areas-two-wings logic, completing the partition

Codes follow the project subset of the national land-use classification guide. This is a concept structure, not a regulatory boundary, ownership conclusion or development-intensity conclusion.


The base is a provisional rough boundary inferred from the announcement's written extents (provisional constraint, official_boundary=false). It supports concept generation, display and self-check only; it is not an official redline, an approval basis or a precise-area basis. All spatial ideas are concept suggestions for professional teams to develop. Areas are recomputed in EPSG:4548; see sources.json.

Fig.3 Detailed design of the three key areas

Zhongzhiyuan / AI Origin Community / Dazhongsi; programme, public space and landmarks

KEY AREAS

Concept proposal · not statutory planning · provisional boundary
zww1992 / jingzhang-warm-line




The base is a provisional rough boundary inferred from the announcement's written extents (provisional constraint, official_boundary=none). It supports concept generation, display and self-check only; it is not an official redline, an approval basis or a precise-area basis. All spatial ideas are concept suggestions for professional teams to develop. Areas are recomputed in EPSG:4548; see sources.json.

Fig.4 Mobility, blue-green network and public space

A continuous system of slow line, warm arcade, stations and stitching links

MOBILITY & BLUE-GREEN

Concept proposal · not statutory planning · provisional boundary
zww1992 / jingzhang-warm-line



System takeaways

- The spine is 9.39 km long: 13 stations sit about 722 m apart, so the 300 m walking catchments stay continuous.
- 13 pedestrian-priority stitching links reconnect the two sides that the railway separated for a century; each link is also a scenario interface and a human stop point.
- Green ratio 19.7%, public-space ratio 5.9%, including a 33.1 ha warm arcade for all-weather winter movement.
- Transit stubs, low-speed delivery and robot resupply share the stations instead of each claiming street space.


The base is a provisional rough boundary inferred from the announcement's written extents (provisional constraint, official_boundary=none). It supports concept generation, display and self-check only; it is not an official redline, an approval basis or a precise-area basis. All spatial ideas are concept suggestions for professional teams to develop. Areas are recomputed in EPSG:4548; see sources.json.

Fig.5 Metric recomputation and evidence chain

Every number is recomputable from the GeoJSON layers in EPSG:4548

METRICS & EVIDENCE

Concept proposal · not statutory planning · provisional boundary
zww1992 / jingzhang-warm-line



Recomputation method and limits

All areas are recomputed in EPSG:4548 (CGCS2000 3-degree zone, CM 117E); the GeoJSON exchange CRS is EPSG:4326. The land-use layer is a complete partition of the submitted boundary; adjacent polygons share identical edge coordinates, their union equals the site area with a gap below 0.001%, and no polygons overlap. Every spatial layer is built on the provisional rough boundary. FAR, building height, building density, green-ratio control, existing floor area and heat-recovery capacity stay marked as pending official data. This package cannot support statutory planning, engineering feasibility or implementation commitments: once official polygons are published the whole chain must be recomputed and all drawings, HTML and metrics reissued.

The base is a provisional rough boundary inferred from the announcement's written extents (provisional constraint, official_boundary=none). It supports concept generation, display and self-check only; it is not an official redline, an approval basis or a precise-area basis. All spatial ideas are concept suggestions for professional teams to develop. Areas are recomputed in EPSG:4548; see sources.json.