

1435 mm

International Open Call · Urban Design

Jing-Zhang 1435 Gauge Belt

GAUGE 1435


From the Standard Gauge to the AI Standard Interface

The Jing-Zhang Standard-Gauge Innovation Belt

“Standards are the track, open source is the roadbed, and talent is the train” — the 1435 mm standard gauge is translated from a railway parameter into a modular system, spatial-structure metaphor and governance language for urban design; the “one track, three stations, two wings” structure, 12 AI scenario cards, 5 user profiles, 6 global cases and 3+ AI pilgrimage landmarks form a display package that is experiential, auditable and ready for professional teams to refine.


Author / Team: DeepslateQAQ □ Date: 2026-08-10 □ Status: Concept design · presentation only

License: COMMUNITY-DISPLAY-ONLY □ Language: English (zh counterpart available)



Master concept diagram · one track, three stations, two wings

Overview · Three-Tier Scope & Concept



Centennial Jing-Zhang Cultural Belt → main track (history); Urban AI Lifestyle Experience Belt → yielding track (human-centred); AI Integration Innovation Belt → track connection (industry).

Tier	Area
Coordinated Research Area	43.61 km ²
Design task	43.61 km ²
Overall Design Area	11.41 km ²
Key-Area Detailed Design	368.4 ha
Urban-renewal framework · regulatory-planning-depth urban design	

Zhongzhiyuan · AI Origin Community · Dazhongsi

Provisional boundary: all three tiers use temporary coarse polygons inferred in EPSG:4548 from the announcement (not official red lines); deviation ≈ 0.02%–1.3%; the package must be recalculated once official polygons are released.

Fig. 1 Master concept (site-overview.png) — one track, three stations, two wings, blue-green system

Concept & Spatial Structure · One Track, Three Stations, Two Wings




Fig. 2 Land-use & spatial structure (land-use-structure.png) — ten functional zones and belts

One track: the Jing-Zhang Heritage Park greenway spine (≈ 9.4 km). Three stations: the **Acceleration Station** (Zhongzhiyuan), the **Origin Station** (AI Origin Community) and the **Scene Station** (Dazhongsì). Two wings: the **service track** (Zhongguancun) and the **living track** (Xiaoyue River), expressed as east/west interface belts within the overall design area.


Track
Full-track independent AI innovation Placement
Accel. track
World-class AI innovation ecosystem
Origin track
AI-scenario enablement paradigm
AI Origin Community
Scene track
Smart, vibrant AI city
Merging + double
Global voice in AI governance
East-west stitch · N-S link
Yielding track

Human governance · human review

Track vocabulary▯Main track · track merging · double tracking · track connection · switching track · yielding track · derailment (governance boundary)

AI pilgrimage landmarks▯▯ Gauge Origin Monument (SN-002, AI Origin Community) ▯ Release Platform (SN-003, Origin Community) ▯ Sleeper Scale Band (9.4 km heritage park; standard milestones every 1435 m) ▯ Honour display (contributor wall / corporate standard board / switching-track directory)

Land-Use Structure



The Overall Design Area is divided into **44 zones** per the land-use classification guide, led by innovation functions: R&D (0802) 32.64%, residential (0701) 28.14%, education (0804) 20.42%, park green (1401) 8.86%, buffer green (1402) 5.59%, commercial (05) 3.97% and plaza (1403) 0.38%; **industry-related land (0802+05) ≈ 36.6%**.

	Area (m ²)
05 Commercial	453,060.2
0701 Residential	3,211,294.7
0802 R&D / Design	3,725,087.7
0804 Education	2,331,085.5
1401 Park green	1,011,753.7
1402 Buffer green	637,543.4
1403 Plaza	43,000.1
	0.38%

Land use is a conceptual partition recomputed from the provisional boundary; recalculate after official red lines and control conditions are released.

Layers: site_boundary(1) · key_areas(3) · land_use(44) · buildings(430 concept) · roads(9) · green_space(18) · public_space(9) · phasing(3) · constraints(4) · scenario_nodes(12)

Fig. 3 Land-use structure (land-use-structure.png)

Mobility, Walking & Blue-Green Space



Key Area 1 · Zhongzhiyuan Acceleration Station (192.1 ha)




Fig. 5 Key-areas index & design tasks (key-areas.png)

Positioning□A garden-type full-stack autonomous innovation acceleration zone — the “testing track” for model training, evaluation, standard-setting and safety governance.

Spatial moves□Open frontage onto the Qinghe (QH blue-green belt), block-based industrial layout (ZZY 0802), green corridor crosses the north end.

Building form□Mid-to-high-rise R&D clusters + laboratory workshops (concept massing, 12–60 m illustrative).

Mobility□North 5th Ring entrance, greenway through-connection, cross-link connections.

AI scenarios□SN-004 acceleration testing ground · SN-005 safety sandbox · SN-012 Global AI Activity Week north node.

Implementation risks□Qinghe blue line & flood-control conditions, FAR controls and ownership pending.

192.9 ha

Area · recomputed (provisional)

Key Area 2 · AI Origin Community Origin Station (104.3 ha)




Fig. 6 Key-areas index & design tasks (key-areas.png)

Positioning□A near-campus technology-transfer and open-source talent community — the origin “from code to product”.

Spatial moves□Campus-park-block walking/cycling stitching (ORIGIN-RD 0802 + ORIGIN-COM 05 + EDU-ORIGIN 0804), release & talent-service space, Origin Station plaza (PLZ-02).

Building form□Mid-to-low-rise mixed blocks (office + talent housing + retail), open ground floors.

Mobility□Metro Line 13 (conceptual RAIL-001) interchange, greenway walking/cycling.

AI scenarios□SN-002 Gauge Origin Monument · SN-003 Release Platform · SN-008 Switching-Track talent market.

Implementation risks□Campus boundary & ownership pending; heritage requirements (Qinghuayuan Station site) await official layers.

104.3 ha

Area : recomputed (provisional)

Key Area 3 · Dazhongsi Scene Station (72.0 ha)




Fig. 7 Key-areas index & design tasks (key-areas.png)

Positioning□A city-level scenario ground for AI-native new business forms and data elements — where “AI is seen, consumed and discussed”.

Spatial moves□Four-quadrant walking connectivity at Dazhongsi Station (PLZ-01 plaza), commercial core (DZS-COM 05) + industry ring (DZS-IND 0802), green corridor crosses the south.

Building form□Mid-to-high-rise commercial complexes + smart-terminal flagship street blocks.

AI scenarios□SN-006 smart-terminal experience street · SN-011 data-element lounge · SN-001 accessible 1435 baseline route (south end).

Implementation risks□Station-integration conditions, commercial-renewal ownership, heritage & urban-character controls pending.

72.0 ha

Area · recomputed (provisional)

Metrics Recalculation & Evidence

The 19 metrics below have **status = known** in metrics.json, recomputed from geometry/*.geojson in EPSG:4548; unknown metrics (FAR, building height, density, setbacks, planning green-ratio controls) are **not fabricated** as official controls are not public.

Metric	Value
Overall Design Area	Unit
Coordinated Research Area	11,412,825.4
Key-Area Count	43,609,232.6
Zhongzhijuan (Accel. Station)	3.0
AI Origin Community (Origin Str)	1,929,201.9
Dazhongsi (Scene Station)	1,043,236.9
GreenSpace Area	720,454.2
Green Ratio	1,649,297.2
Public Space Area	14.45%
Public Space Ratio	43,000.0
Concept Building Footprint	0.38%
Concept Road Network Length	2,649,208.0
Greenway Spine Length	27,901.9
AI Scenario Nodes	9,405.3
Industry Land Ratio (0802+05)	12.0
SN-001 ... SN-012	36.61%
Residential Land Ratio (0701)	28.14%
Near-Term PHASE-001 Area	2,087,143.8
Mid-Term PHASE-002 Area	4,798,000.5
Far-Term PHASE-003 Area	4,943,737.5
	≈ 479.8 ha
	≈ 494.4 ha

Metrics Evidence Panel — Key Data at a Glance

GAUGE 1435 · The Jing-Zhang Standard-Gauge Innovation Belt
— from standard gauge to Standard AI interfaces




Fig. 5 Metrics evidence panel (metrics-evidence.png)

known: recomputed areas deviate ≈ 0.02%–1.3% from announced values; **unknown:** FAR, height, density, setbacks, planning green-ratio controls await official conditions.

Implementation Phasing & Operation



Declaration · Sources · Layers

1. This drawing set is **for presentation only** and does not replace the authoritative GeoJSON / metrics.json in the submission package.
2. All boundaries are **provisional substitute boundaries (not official planning red lines)**, inferred from the announcement's verbal four-to boundaries and announced areas in EPSG:4548; the whole package must be recalculated once the official GIS/CAD red lines are released.
3. Land use, phasing, scenarios and operations are **concept proposals** for professional teams to refine; control indicators such as FAR, height and density await formal control conditions.
4. Primary basis: the Prequalification Announcement for the Centennial Jing-Zhang AI Innovation Belt Urban Design (Haidian Branch, Beijing Municipal Commission of Planning and Natural Resources) and the maintainer's brief/site-package.
5. License: COMMUNITY-DISPLAY-ONLY. Author: DeepslateQAQ. Generated: 2026-08-10.




Fig. 10 Evidence chain & package structure (site-overview.png)