


Origin & Embodiment — Overall structure and naming system

Overall structure: one spine, three origins, four testbeds

FIG 01 / STRUCTURE

Centennial Jingzhang AI Innovation Belt · Origin & Embodiment — concept suggestion, not statutory planning



Structural elements

- Heritage park green spine
- Key areas (three origins)
- Embodied zone plazas (testbeds)
- Slow-mobility spine
- East-west stitching links
- Provisional extent (unofficial)

Design judgements

- 1 | The 9 km linear heritage park is read as a continuous test line rather than a scenic band: it is the only corridor in the belt able to offer uninterrupted, closable and gradable human-machine coexistence.
- 2 | Each key area carries one kind of origin: Zhongzhiyuan = technical autonomy, Origin Community = open-source collaboration, Dazhongsi = market and consumption.
- 3 | The four testbeds appear as plazas rather than gated parks, so embodied validation happens in public view instead of behind walls.
- 4 | East-west stitching links answer the rail-legacy dead ends and are this proposal's spatial answer to 'stitch east-west, connect north-south'.


Boundaries are provisional rough extents derived from the announcement's textual limits (provisional_constraint, not an official redline); the dashed line is a scope hint only. All areas and metrics must be recomputed once official boundaries are released. Sources: brief/site-package/geometry/provisional_boundaries.geojson, geometry/*-geojson, metrics.json.

Land-use structure and embodied zone grading (EUZ L1–L4)


FIG 02 / LAND USE & GRADING

Land-use polygons fully cover the submitted boundary (coverage 1.0000) with human-machine intensity grading overlaid

A | Land-use structure



B | Embodied zone grading EUZ L1–L4



Land-use classes (project subset)

- Research 0802
- Commercial services 05
- Urban housing 0701
- Residential 07
- Community service facilities 0702
- Culture 0803
- Education 0804
- Park green space 1401
- Plaza 1403
- Reserved land 16

Embodied urban zone grading

- L1 Pedestrian-priority zone
- L2 Shared human-machine zone
- L3 Robot-resident zone
- L4 Autonomous validation zone

Why grade the space

It turns 'AI deployment' into a manageable spatial institution: each level fixes speed limits, operating hours, kerb and paving treatment, takeover-point density, public notice and the human review owner.

L1 pedestrian-priority covers housing and education frontages where robots pass only under restriction; L4 autonomous validation is concentrated in Zhongzhiyuan, away from housing

Levels can be raised or lowered after assessment, avoiding a one-off 'smart demonstration belt' that cannot be rolled back.

L3 plus L4 together take 26.0% of the scope; the rest stays pedestrian-priority or shared — an embodied city does not hand the street to machines.

Land-use suggestions are conceptual and expressed with the project subset of the national land-use classification guide; they are not FAR, building-height, road-width or density conclusions. The grading is an instrument proposed by this submission and requires professional and authority assessment before use.


Origin & Embodiment — Embodied zone grading and key areas

Detailed design index for the three key areas

FIG 03 / KEY AREAS

Zhongzhiyuan · AI Origin Community · Dazhongsi | function, spatial move, embodied scenario, dependency


A. Zhongzhiyuan AI Acceleration Area



approx. 192.1 ha (announced) · L4 autonomous validation

- Spatial move: strengthen the Qinghe ecological frontage and form a closable internal autonomous loop
- Embodied scenario: whole-machine and component joint validation, standards and safety assessment open days
- Dependency: Qinghe blue line, park ownership, energy and compute access


B. Beijing AI Origin Community



approx. 104.3 ha (announced) · L3 robot-resident zone

- Spatial move: three-way slow-mobility stitching between campus, park and neighbourhood; add release and talent housing
- Embodied scenario: open-source release hall, campus-adjacent resident service robots, night collaboration
- Dependency: campus boundaries and authorisation, housing frontage negotiation, ground-floor use adjustment

C. Dazhongsi AI Industry Cluster



approx. 72.0 ha (announced) · L3 station-city unit

- Spatial move: four-quadrant pedestrian connection at Dazhongsi station; the plaza carries station-city embodied transfer
- Embodied scenario: last-metre delivery and transfer, smart terminal experience, data-element reception hall
- Dependency: station integration, municipal utilities, coordination with commercial owners


Dark = indicative footprints · Orange = embodied plazas · Green = park · Blue dashed = provisional key-area extent · panels are not at a common scale

Key-area extents are provisional rough extents (provisional_constraint); rectangular edges must not be read as parcel boundaries or road redlines. Building footprints are indicative study objects, not retain/renovate/demolish conclusions.

Slow mobility, transfer and blue-green public space system

FIG 04 / MOBILITY & BLUE-GREEN

One spine + 8 east-west stitching links + 6 embodied transfer loops | network length approx. 26.0 km



System elements

- Park and ecological finger greens
- Embodied zone plazas
- Slow-mobility spine (continuous test line)
- East-west stitching links
- Embodied transfer loops
- Provisional extent (unofficial)

System logic

A continuous spine means continuous testing. Low-speed vehicles complete long-distance validation on one route without repeatedly crossing traffic.

Stitching links turn 'reachable along the corridor' into 'reachable from both sides', upgrading the park from a scenic band to a daily commuting and delivery backbone.

Transfer loops turn plazas into bounded operating units: entering means accepting the grading rules, leaving means returning to a pedestrian-priority environment.

Green ratio 17.8%, public-space ratio 2.3%; area is not the goal — continuity and manageability are.

Alignments are concept suggestions and do not account for road redlines, utilities, fire access or traffic engineering conditions; rail station relationships must be verified with the rail authority before deepening.